STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 - CHARLOTTE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
EB	MM, 1.100, RT	A	VW-276H	30	30		DRIFTING SNOW	6.25								1		X								INSTALL NEW SIGN AND POST IN CLOSED POSITION ON THE SAME LOCATION OF POLE #101/69/11163		8	
WB	MM, 1.810, LT	F	VW-276H	30	30		DRIFTING SNOW	6.25								1		X								INSTALL NEW SIGN AND POST IN CLOSED POSITION ACROSS FROM POLE #93/124		8	
EB	MM, 2.190, RT	A	VD-018	30	18		East Charlotte Hinesburg 4	3.75								1		X								INSTALL NEW SIGN AND POST 158 FT SOUTH AND ACROSS FROM POLE #2149		8	
EB	MM, 2.220, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS ACROSS FROM POLE #2149	X		
EB	MM, 2.230, RT	A	W3-1	36	36								X		X											REMOVE EXISTING SIGN AND POSTS 75 FT NORTH AND ACROSS FROM POLE #2149.			
WB	MM, 2.250, LT	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST 158 FT NORTH FROM POLE #2149.	X		
EB	MM, 2.280, RT	A	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 317 FT NORTH AND ACROSS FROM POLE #2149	X		
		A	R3-1	12	8		4-WAY						X													REMOVE EXISTING PLAQUE BELOW R1-1 SIGN ON THE SAME POST			
		A	R3-1P	18	6		ALL WAY	0.75																		INSTALL NEW PLAQUE BELOW THE REPLACED R1-1 SIGN ON THE SAME POST	X		
WB	MM, 2.280, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST NEXT TO THE PARKING AREA	X		
		H	R3-1	12	8		4-WAY						X													REMOVE EXISTING PLAQUE BELOW R1-1 SIGN ON THE SAME POST			
		H	R1-3P	18	6		ALL WAY	0.75																		INSTALL NEW PLAQUE BELOW THE REPLACED R1-1 SIGN ON THE SAME POST	X		
WB	MM, 2.280, LT +350 FT, LT	H	W3-1	36	36			9.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS NEXT TO PARKING AREA ON SPEAR STREET	X		
EB	MM, 2.290, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST AT THE CORNER OF SPEAR STREET AND HINESBURG ROAD AND DIAGONAL FROM THE PARKING AREA	X		
		D	R3-1	12	8		4-WAY						X													REMOVE EXISTING PLAQUE BELOW R1-1 SIGN ON THE SAME POST			
		D	R1-3P	18	6		ALL WAY	0.75																		INSTALL NEW PLAQUE BELOW THE REPLACED R1-1 SIGN ON THE SAME POST	X		
										EA	EA	EA	EA 8	EA	EA 5		FT	FT 165	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 60.25	SF	EA 8				EA 5		EA 11	FT 165			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
CHARLOTTE TRAFFIC SIGN SUMMARY 4

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 24 OF 54