STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6 - CHARLOTTE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM, 3.920, RT	A	W1-2R	30	30								X		X											REMOVE EXISTING SIGN AND POST NEXT TO POLE #2/166			
		A	W13-1P	18	18								X													REMOVE EXISTING BELOW PLAQUE W1-2R SIGN ON THE SAME POST			
EB	MM, 3.920, RT	A	W1-4L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST NEXT TO POLE #2/166	X		
		A	W13-1P	18	18			2.25																		INSTALL NEW PLAQUE BELOW W1-4L SIGN ON THE SAME POST	X		
							CHURCH HILL ROAD																						
WB	MM, 0.030, RT	A	W3-1	36	36								X		X X											REMOVE EXISTING SIGN AND 2 POSTS 158 FT NORTH FROM POLE #GMP/5/CTC/2/28			
		A	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 158 FT NORTH FROM POLE #GMP/5/CTC/2/28	X		
		A	W16-8AP	48	15			5.00																		INSTALL NEW PLAQUE BELOW W2-1 SIGN ON THE SAME 2 POSTS		8	
NB	MM, 0.070, RT	A	W1-1R	30	30								X		X											REMOVE EXISTING SIGN AND POST 370 FT NORTH FROM POLE #GMP/5/CTC/2/28			
		A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 370 FT NORTH FROM POLE #GMP/5/CTC/2/28	X		
NB	MM, 1.100, RT	A	R1-1	30	30			6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST NEXT TO POLE #GMP/52	X		
		A	R1-3	12	8								X													REMOVE EXISTING PLAQUE BELOW R1-1 SIGN ON THE SAME POST			
		A	R1-3P	18	6			0.75																		INSTALL NEW PLAQUE BELOW THE REPLACED R1-1 STOP SIGN ON SAME POST	X		
SB	MM, 1.100, LT	H	R1-1	30	30			6.25					X		X	1		X								REPLACE THE EXISTING SIGN AND POST 264 FT FROM POLE #GMP/2 ON MUSEUM ROAD	X		
		H	R1-3	12	8								X													REMOVE EXISTING PLAQUE BELOW R1-1 SIGN ON THE SAME POST			
		H	R1-3P	18	6			0.75																		INSTALL NEW PLAQUE BELOW THE REPLACED R1-1 SIGN ON THE SAME POST	X		
										EA	EA	EA	EA 8	EA	EA 6		FT	FT 105	FT		LB	LB	LB	LB					
							SHEET TOTALS	SF 45.50	SF	EA 8				EA 6		EA 7	FT 105			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
CHARLOTTE TRAFFIC SIGN SUMMARY 6

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 26 OF 54