STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - CAMBRIDGE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM, 0.010, LT	F	R1-1	30	30		STOP			X				X												RETAIN EXISTING STOP SIGN AND POST			
EB	MM, 0.032, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 10 FT WEST OF POLE #V/E/COOP/13/2A/10X	X		
WB	MM, 0.070, LT	F	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 195 FT EAST AND ACROSS FROM POLE #V/E/COOP/13/2A/10X	X		
EB	MM, 0.249, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST	X		
EB	MM 0.320, RT TO MM 0.386, RT	A B		6	8		(6) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (6) BACK-TO-BACK 60 FT APART ON 3 POSTS, INSTALL FIRST DELINEATOR 127 FT WEST OF MAILBOX #317		7	
EB	MM, 0.356, RT	A	S3-2	36	36	FYG	SCHOOL BUS TURN AHEAD	9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 65 FT EAST OF MAIL BOX #317	X		
EB	MM, 0.455, RT	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						X		X											REMOVE EXISTING SIGN AND POST			
EB	MM, 0.464, RT	A	VW-060	30	30		HIDDEN DRIVE						X		X											REMOVE EXISTING SIGN AND POST			
EB	MM, 0.478, RT	A	VW-054A	30	30		HIDDEN DRIVES RIGHT	6.25								1		X								INSTALL NEW SIGN AND POST 106 FT WEST AND ACROSS FROM POLE #13/2A3X/8-3/9		8	
WB	MM, 0.579, LT	F	VW-060	30	30		HIDDEN DRIVES	6.25								1		X								INSTALL NEW SIGN AND POST 227 FT WEST OF POLE #V/E/COOP/13/2A/11		8	
WB	MM, 0.636, LT	F													X											REMOVE EMPTY POST			
WB	MM, 0.641, LT	F	VW-059	30	30		HIDDEN DRIVE						X		X											REMOVE EXISTING SIGN AND POST 100 FT EAST OF POLE #V/E/COOP/13/2A/11			
WB	MM, 0.834, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								REPLACE EXISTING SIGN AND POST THAT IS 42 FT WEST OF POLE #13/10/17	X		
EB	MM, 0.853, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 58 FT EAST AND ACROSS FROM POLE #13/10/17	X		
		A	W13-1	18	18		35 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-2L SIGN ON THE SAME POST	X		
										EA 1	EA	EA	EA 4	EA 1	EA 5		FT	FT 150	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 54.00	SF	EA 5				EA 6		EA 10	FT 150			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
CAMBRIDGE TRAFFIC SIGN SUMMARY 1

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 17 OF 54