STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – FERRISBURGH

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL IN SHS	SIGN DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM, 0.120, RT	A	R2-1	24	30		SPEED LIMIT 35			X				X												RETAIN EXISTING SL-35 SIGN, CUT TOP OF POST SO AS TO NOT BE ABOVE THE SIGN.			
EB	MM, 0.240, RT	A	W2-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 15 FT WEST OF POLE *GMP/67/CTC/4R	X		
		A	W16-8P	30	8		MT Philo Rd	1.68																		INSTALL NEW PLAQUE BELOW W2-2L SIGN ON THE SAME POST		8	
EB	MM, 0.320, RT	C	W1-7	48	24			8.00					X		X	2		X								REPLACE EXISTING SIGN AND INSTALL NEW ON 2 POSTS AT END OF GUARDRAIL ACROSS FROM MT PHILO RD	X		
EB	MM, 0.360, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 222 FT WEST OF POLE *GMP/72/CTC/47	X		
WB	MM, 0.392, LT	F	W2-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 50 FT WEST AND ACROSS FROM POLE *GMP/72/CTC/47	X		
		F	W16-8P	30	8		MT Philo Rd	1.68																		INSTALL NEW PLAQUE BELOW W2-2R SIGN ON THE SAME POST		8	
EB	MM, 0.573, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 903 FT EAST OF POLE *GMP/72/CTC/47	X		
WB	MM, 0.573, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 903 FT EAST AND ACROSS FROM POLE *GMP/72/CTC/47	X		
							MT. PHILO ROAD																						
NB	MM, 0.010, RT	A	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 50 FT NORTH OF THE INTERSECTION WITH OLD HOLLOW RD	X		
SB	MM, 0.010, LT	E	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 50 FT NORTH OF INTERSECTION WITH OLD HOLLOW RD ACROSS FROM PREVIOUSLY INSTALLED SIGN ASSEMBLY	X		
SB	MM, 0.113, LT	F	W3-1	36	36			9.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS 50 FT SOUTH OF POLE *GMP/4	X		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft	SQUARE STEEL (in) 2.00 lb/ft	SQUARE STEEL (in) 2.50 lb/ft	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft	TUBULAR STEEL O/(in) 3.50 lb/ft	TUBULAR STEEL O/(in) 4.00 lb/ft	TUBULAR STEEL O/(in) 5.00 lb/ft
			EA 1	EA	EA	EA 7	EA 1	EA 7			FT 165	FT		LB	LB	LB	LB
SHEET SUBTOTALS	SF 60.36	SF	EA 8				EA 8		EA 11		FT 165		EA	LB			

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
FERRISBURGH TRAFFIC SIGN SUMMARY 1

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 33 OF 54