STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - FAIRFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS FT'B FT	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM, 2.247, RT	A	VW-059	30	30		HIDDEN DRIVES LEFT	6.25								1		X								INSTALL NEW SIGN AND POST 189 FT NORTH OF POLE #25/6/13/20/20/54		9	
SB	MM, 2.396, LT	G	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	5.00								1		X								INSTALL NEW SIGN AND POST 69 FT NORTH OF AND ACROSS FROM MAIL BOX 2366		9	
SB	MM, 2.461, LT	G	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	5.00								1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #5/C/16/51		9	
NB	MM, 2.600, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 148 FT SOUTH OF AND ACROSS FROM POLE #4D/25C/18A	X		
SB	MM, 2.600, LT	F	VW-622	30	30		RECREATIONAL AREA	6.25								1		X								INSTALL NEW SIGN AND POST 148 FT SOUTH OF FROM POLE #4D/25C/18A		9	
		F	W7-3a	24	18		NEXT 1/2 MILE	3.00																		INSTALL NEW PLAQUE BELOW VW-622 ON THE SAME POST	X		
SB	MM, 2.708, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 422 FT NORTH OF POLE #4D/25C/18A	X		
NB	MM, 2.710, RT	A	W16-8P	24	8		Pond Rd						X		X											REMOVE EXISTING SIGN AND POST			
NB	MM, 2.714, RT	A/B	D3-1	36	12		Pond Rd	3.00								1		X								INSTALL NEW STREET NAME SIGN ABOVE THE R1-1 SIGN 454 FT NORTH OF AND ACROSSS FROM POLE #4D/25C/18A		9	
		A	R1-1	30	30		STOP	6.25																		INSTALL NEW SIGN BELOW D3-1 SIGN ON THE SAME POST 454 FT NORTH OF AND ACROSSS FROM POLE #4D/25C/18A	X		
NB	MM, 2.723, CL	J	W1-7	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 502 FT NORTH OF POLE #4D/25C/18A DIRECTLY ACROSS FROM INTERSECTION IN FRONT OF APPROACHING TRAFFIC ON POND RD	X		
NB	MM, 2.749, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #NET/20/46	X		
SB	MM, 2.789, LT	F	W2-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 211 FT NORTH OF POLE #NET/20/46	X		
		F	W16-8P	24	8		Pond Rd	1.34																		INSTALL NEW PLAQUE BELOW W2-2R SIGN ON THE SAME POST		9	
							SHEET SUBTOTALS	SF 69.34	SF	EA 1	EA	EA	EA 1	EA 1	EA 1	EA 12	FT	FT 180	FT	EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
FAIRFIELD TRAFFIC SIGN SUMMARY 2

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 30 OF 54