STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – HINESBURG CHARLOTTE RD.

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O (in) FOUNDATION	TUBULAR STEEL O (in) 3.00 lb/ft 7.60	TUBULAR STEEL O (in) 3.50 lb/ft 9.00	TUBULAR STEEL O (in) 4.00 lb/ft 10.80	TUBULAR STEEL O (in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL IN SHS	SIGN DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
WB	MM 0.000, LT	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST AT TOWN LINE 150 FT +/- WEST AND ACROSS FROM MAILBOX	X		
EB	MM 0.000, RT	C	VD-024	72	10		Hinesburg | Charlotte	5.00								2		X								INSTALL NEW SIGN ON 2 POSTS AT TOWN LINE 150 FT +/- WEST AND ACROSS FROM MAILBOX		9	
EB	MM 0.010, LT	A	VR-017	24	30		LEGAL LOAD LIMIT 55,000 POUNDS	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 50 FT EAST OF TOWN LINE		6	
		A	R2-1	24	30		SPEED LIMIT 45	5.00																		INSTALL NEW SIGN BELOW VR-017 SIGN ON THE SAME POST	X		
EB	MM 0.020, RT	A	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE EXISTING SIGN AND POST			
EB	MM 0.025, RT	B	WI-6L	48	24		←	8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 26 FT EAST OF WELCOME TO HINESBURG SIGN	X		
WB	MM 0.040, LT	E	WI-6R	48	24		→	8.00								2		X								INSTALL NEW SIGN ON 2 POSTS PUT 50 FT EAST OF MAILBOX	X		
WB	MM 0.080, LT	F	WI-4L	30	30		↰	6.25								1		X								INSTALL NEW SIGN AND POST 100 FT EAST AND ACROSS FROM POLE #GMP/3	X		
		F	WI3-1P	18	18		35 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-4L SIGN ON THE SAME POST	X		
WB	MM 0.090, LT	F	WI-2L	30	30		↰						X		X											REMOVE EXISTING SIGN AND POST			
		F	WI3-1P	18	18		25 M.P.H.						X													REMOVE EXISTING PLAQUE BELOW WI-2L SIGN ON THE SAME POST			
EB	MM 0.090, RT	A	R2-1	24	30		SPEED LIMIT 45						X		X											REMOVE EXISTING SIGN AND POST			
WB	MM 0.240, LT	F	VW-276H	30	30		DRIFTING SNOW	6.25								1		X								INSTALL NEW SIGN AND POST IN CLOSED POSITION ACROSS FROM POLE #GMP/9		8	
EB	MM 0.240, RT TO MM 0.300, RT	A B		6	8		(8) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (8) BACK-TO-BACK 60 FT APART ON 4 POSTS. INSTALL FIRST JUST EAST OF POLE #GMP/9		7	
EB	MM 0.370, RT	A	WI-4L	30	30		↰	6.25								1		X								INSTALL NEW SIGN AND POST 25 FT WEST OF POLE #GMP/13	X		
										EA	EA	EA	EA 5	EA	EA 4		FT	FT 165	FT					LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 57.00	SF	EA 5				EA 4		EA 11	FT 165			EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HINESBURG CHARLOTTE ROAD TSS 1

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 35 OF 54