STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - HINESBURG HOLLOW RD.

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O (in) FOUNDATION	TUBULAR STEEL O (in) 3.00 lb/ft 7.60	TUBULAR STEEL O (in) 3.50 lb/ft 9.00	TUBULAR STEEL O (in) 4.00 lb/ft 10.80	TUBULAR STEEL O (in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL IN SHS	SIGN DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
EB	MM, 0.020, RT	A	R2-1	24	30		SPEED LIMIT 45	5.00								1		X								INSTALL NEW SIGN ACROSS FROM POLE #GMP/1	X		
		A	VR-017	24	30		LEGAL LOAD LIMIT 55,000 POUNDS	5.00					X		X											REPLACE EXISTING SIGN AND POST ON THE SAME POST ONE, PUT BELOW SPEED LIMIT 45 SIGN		6	
EB	MM, 0.060, RT	A	R2-1	24	30		SPEED LIMIT 45						X		X											REMOVE EXISTING SIGN AND POST 260 FT EAST AND ACROSS FROM POLE #GMP/1	X		
WB	MM, 0.090, LT	F	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 420 FT EAST OF POLE #GMP/1	X		
WB	MM, 0.120, LT	F	W3-1	30	30								X		X											REMOVE EXISTING SIGN AND POST 581FT EAST OF POLE #GMP/1			
EB	MM, 0.180, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 265 FT EAST AND ACROSS FROM POLE #GMP/3	X		
WB	MM, 0.270, LT	F	W1-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 50 FT WEST OF SAND PIT DRIVE WITH STEEL GATE	X		
EB	MM, 0.370, RT	A	VR-023B	24	36		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	6.00								1		X								INSTALL NEW SIGN AND POST ACROSS FROM SAND PIT DRIVE IN PULL OFF		9	
EB	MM, 0.465, RT	A	W1-4L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 30 FT EAST OF END OF GUARDRAIL	X		
WB	MM, 0.500, LT	F	VR-023B	24	36		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	6.00								1		X								INSTALL NEW SIGN AND POST IN PULL OFF		9	
WB	MM 0.515, LT TO MM 0.610, LT						(14) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (14) BACK-TO-BACK 60 FT APART ON 7 POSTS, INSTALL FIRST DELINEATOR 80 FT EAST OF CENTER OF PULL OFF		8	
WB	MM, 0.690, LT	F	W1-4L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 25 FT WEST AND ACROSS FROM POLE #33A/40	X		
WB	MM, 0.700, LT	F	VR-023B	24	36		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	6.00								1		X								INSTALL NEW SIGN AND POST 25 FT EAST AND ACROSS FROM POLE #33A/40		9	
EB	MM, 0.700, RT	A	R2-1	24	30		SPEED LIMIT 45	5.00								1		X								INSTALL NEW SIGN AND POST 25 FT EAST OF POLE #33A/40	X		
							SHEET SUBTOTALS	SF 67.00	SF	EA 3				EA 3		EA 11	FT 165			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HINESBURG HOLLOW ROAD TSS 1

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 40 OF 54