STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 – HINESBURG CHARLOTTE RD.

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 1.222, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST EAST OF POLE #GMP/45/CTC/6/45	X		
EB	MM 1.230, RT	C	W1-6L	48	24	F-Y	←	8.00					X		X X	2		X								REPLACE EXISTING SIGN ON 2 POSTS 60 FT EAST OF POLE #GMP/45/CTC/6/45	X		
WB	MM 1.290, RT	B	VW1-1MbR	36	36	F-Y	↱	9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 20 FT EAST OF POLE #43		9	
		B	W13-1P	18	18		20 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW VW1-1MbR SIGN ON THE LEFT HAND POST	X		
EB	MM 1.480, RT	A	W1-2R	30	30		↱						X		X											REMOVE EXISTING SIGN AND POST			
		A	W13-1P	18	18		25 M.P.H.						X													REMOVE EXISTING PLAQUE BELOW W1-2R SIGN ON THE SAME POST			
EB	MM 1.480, RT	A	VW1-1MbR	36	36	F-Y	↱	9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 20 FT EAST OF POLE #GMP53		9	
		A	W13-1P	18	18	F-Y	20 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW VW1-1MbR SIGN ON THE LEFT HAND POST	X		
WB	MM 1.530, LT	G	W1-6L	48	24	F-Y	←	8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 270 FT EAST AND ACROSS FROM POLE #GMP/53	X		
WB	MM 1.540, LT	H	R1-2	36	36		YIELD	4.50								2		X								INSTALL NEW SIGN ON 2 POSTS 327 FT EAST AND ACROSS FROM POLE #GMP/53	X		
WB	MM 1.542, LT	G	W1-6R	48	24	F-Y	→	8.00					X		X X	2		X								REPLACE EXISTING SIGN ON 2 POSTS IN ISLAND /INTERSECTION WITH LEAVENS WORTH ROAD	X		
WB	MM 1.542, LT	H	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST IN ISLAND FOR EASTBOUND LEG OF TRAFFIC	X		
WB	MM 1.542, LT	F	W1-6L	48	24	F-Y	←	8.00								2		X								INSTALL NEW SIGN ON 2 POSTS IN ISLAND FACING WESTBOUND TRAFFIC	X		
EB	MM 1.590, RT	A	R2-1	24	30		SPEED LIMIT 45	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 20 FT +/- WEST OF POLE #GMP/57/CTC/33	X		
WB	MM 1.600, RT	B	VW1-1MaL	36	36	F-Y	↰	9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 20 FT EAST OF POLE #GMP/57/CTC/33		9	
		B	W13-6P	18	18	F-Y	20 M.P.H.	2.25																		INSTALL NEW SIGN ON 2 POSTS BELOW W1-1MOL SIGN ON THE RIGHT HAND POST	X		
										EA	EA	EA	EA 6	EA	EA 7		FT	FT 285	FT		LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 87.75	SF	EA 6				EA 7		EA 19	FT 285			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HINESBURG CHARLOTTE ROAD TSS 3

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 37 OF 54