

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL O/(in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL																
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER												
																														lb/ft	lb/ft	lb/ft	lb/ft								
WB	MM, 1.341, LT	F	R2-1	24	30			5.00							1		X							INSTALL NEW SIGN AND POST 50 FT WEST OF EXISTING LOCATION	X																
WB	MM, 1.350, LT	F	R2-1	24	30																			REMOVE EXISTING SIGN AND POST																	
EB	MM, 1.390, RT	A	WI-4L	30	30			6.25							1		X							INSTALL NEW SIGN AND POST 50 FT WEST OF WILDLIFE MANAGEMENT DRIVE	X																
EB	MM, 1.420, RT	A	R2-1	24	30																			REMOVE EXISTING SIGN AND POST																	
EB	MM, 1.540, RT	A	R2-1	24	30			5.00							1		X							INSTALL NEW SIGN AND POST 106 FT EAST OF AND ACROSS FROM MAILBOX 1515	X																
WB	MM, 1.540, LT	F	WI-4L	30	30			6.25							1		X							INSTALL NEW SIGN AND POST ADJACENT TO FENCE GATE 106 FT EAST OF MAILBOX 1515	X																
EB	MM, 2.280, RT	A	VW-054	30	30			6.25							1		X							INSTALL NEW AND POST 400 FT +/- WEST OF MAILBOX 2312			8														
EB	MM, 2.340, RT	A	VR-023B	24	36			6.00							1		X							INSTALL NEW SIGN AND POST 100 FT +/- EAST OF MB2312			9														
EB	MM, 2.430, RT	A	WI-2L	30	30			6.25							1		X							INSTALL NEW SIGN AND POST 25 FT WEST OF END OF GUARDRAIL CURL	X																
WB	MM, 2.610, LT	F	WI-2R	30	30			6.25							1		X							INSTALL NEW SIGN AND POST 130 FT EAST OF AND ACROSS FROM END OF GUARD RAIL FLARE	X																
WB	MM, 2.740, LT	F	R2-1	24	30																			REMOVE EXISTING SIGN AND POST																	
WB	MM, 2.780, LT	F	TOWN SIGN	24	30																			REMOVE EXISTING SIGN AND POST																	
		F	VR-017	24	30																			REMOVE EXISTING SIGN																	
WB	MM, 2.780, LT	F	TOWN SIGN	36	30						X				2		X							INSTALL SALVAGED SIGN ON 2 POSTS 74 FT EAST OF POLE # 33A/5																	
WB	MM, 2.795, LT	F	TOWN SIGN	36	30						X													REMOVE SIGN AND POSTS AND SALVAGE TO MM 2.780																	
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".																																									
SHEET SUBTOTALS								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA											
								47.25		8	6	10	150	150	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA											
																						PROJECT NAME: STATEWIDE NORTHWEST REGION		PROJECT NUMBER: STP HRRR(9)		FILE NAME: d10k318_wrk.dgn		PLOT DATE: 22-OCT-2012		PROJECT LEADER: JLS		DRAWN BY: ITS		DESIGNED BY: NLA		CHECKED BY: JLS		HINESBURG HOLLOW ROAD TSS 2		SHEET 41 OF 54	