STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 – HINESBURG CHARLOTTE RD.

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 1.600, LT	F	VW1-1MaL	36	36	FY		9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 20 FT +/- EAST AND ACROSS FROM POLE #GMP/57/CTC/33		9	
		F	W13-1P	18	18	FY		2.25																		INSTALL NEW PLAQUE BELOW VW1-1MbL SIGN ON THE LEFT HAND POST	X		
EB	MM 2.210, RT TO MM 2.270, RT	A B		6	8		(8) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (8) BACK-TO-BACK 60 FT APART ON 4 POSTS, INSTALL FIRST DELINEATOR 50 FT WEST OF POLE #GMP/75/CTC/6/14		7	
WB	MM 2.470, LT	F	R2-1	24	30			5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 238 FT WEST OF STELLA RD	X		
WB	MM 2.510, LT	H	R1-1	30	30			6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST JUST WEST OF STELLA RD	X		
EB	MM 2.530, RT	A	W3-1	30	30								X		X											REMOVE EXISTING SIGN AND POST			
EB	MM 2.530, RT	A	W3-3	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 80 FT EAST AND ACROSS FROM STELLA RD	X		
							BALDWIN ROAD																						
NB	MM 0.055, RT	A	W3-1	36	36			9.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS 50 FT SOUTH AND ACROSS FROM POLE #GMP/2/2	X		
SB	MM 0.020, LT	F	R2-1	24	30			5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 50 FT SOUTH OF POLE #GMP/2/2	X		
							SLIP RAMP FOR LEAVENWORTH ROAD																						
NB	MM 0.010, RT	A	R1-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST ON RAMP FOR NORTH BOUND TRAFFIC ONTO LEAVEN WORTH ROAD	X		
							SHEET SUBTOTALS	SF 51.75	SF	EA 5				EA 5		EA 10		FT 150		EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: d10k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HINESBURG CHARLOTTE ROAD TSS 4

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 38 OF 54