STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - HYDE PARK

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS FT'B FT'	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O (in) FOUNDATION	TUBULAR STEEL O (in) 3.00 lb/ft 7.60	TUBULAR STEEL O (in) 3.50 lb/ft 9.00	TUBULAR STEEL O (in) 4.00 lb/ft 10.80	TUBULAR STEEL O (in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL IN SHS	SIGN DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM, 0.010, RT	A	R2-5A	30	30		REDUCE SPEED AHEAD						X		X											REMOVE SIGN AND POST 422 FT SOUTH OF POLE #MW&LD/672/13			
NB	MM, 0.160, RT	A	W8-3	30	30		PAVEMENT ENDS	6.25								1		X								INSTALL NEW SIGN AND POST 370 FT NORTH OF POLE #MW&LD/672/13	X		
NB	MM, 0.640, RT	A	W1-3R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 120 FT SOUTH AND ACROSS FROM POLE #36/9	X		
		A	W13-1	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-3R SIGN ON THE SAME POST	X		
NB	MM, 0.702, RT	C	W1-7	48	24			8.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS 53 FT NORTH AND ACROSS FROM POLE #1/2	X		
SB	MM, 0.900, LT	F	W1-4R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 1100 FT NORTH OF POLE #1/2	X		
		F	W13-1	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-4R SIGN ON THE SAME POST	X		
							GREEN RIVER RESERVOIR DAM ROAD																						
EB	MM, 0.010, RT	A	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST 25 FT WEST OF POLE #1/2	X		
WB	MM, 0.020, LT	F	W14-2	30	30		NO OUTLET	6.25								1		X								INSTALL NEW SIGN AND POST 105 FT WEST OF GARFIELD ROAD INTERSECTION	X		
WB	MM, 0.068, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 359 FT WEST OF GARFIELD ROAD INTERSECTION	X		
EB	MM, 0.068, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 359 FT WEST OF GARFIELD ROAD INTERSECTION ACROSS FROM SPEED LIMIT 35 SIGN	X		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

	NEW SIGNS "A"	NEW SIGNS FT'B FT'	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL 1.75 lb/ft 1.88	SQUARE STEEL 2.00 lb/ft 2.42	SQUARE STEEL 2.50 lb/ft 3.35	TUBULAR STEEL FOUNDATION	TUBULAR STEEL 3.00 lb/ft 7.60	TUBULAR STEEL 3.50 lb/ft 9.00	TUBULAR STEEL 4.00 lb/ft 10.80	TUBULAR STEEL 5.00 lb/ft 14.60
			EA	EA	EA	EA 2	EA	EA 2			FT	FT 150	FT		LB	LB	LB	LB
SHEET SUBTOTALS	SF 57.75	SF	EA 2				EA 2		EA 10		FT 150		EA		LB			

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HYDE PARK TRAFFIC SIGN SUMMARY 1

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 44 OF 54