STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES	TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
50	50		CY	EARTH BORROW	203.30	EST.			
1	1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
10	10		TON	AGGREGATE SHOULDERS	402.12	EST.			
30	30		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
8	8		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
30	30		HR	TRUCK RENTAL	608.37	EST.			
5	5		HR	LOADER RENTAL, TYPE I	608.40	EST.			
287.5	287.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
3	3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
64.5	64.5		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
300	300		HR	FLAGGERS	630.15	EST.			
1	1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
1	1		LS	TRAFFIC CONTROL	641.10	-			
1100	1100		LF	4 INCH WHITE LINE	646.20	43.24			
1000	1000		LF	4 INCH YELLOW LINE	646.21	5.28			
180	180		LF	24 INCH STOP BAR	646.26	-			
209	209		EACH	LETTER OR SYMBOL	646.30	-			
15	15		LB	SEED	651.15	EST.			
15	15		LB	FERTILIZER	651.18	EST.			
0.3	0.3		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
0.75	0.75		TON	HAY MULCH	651.25	EST.			
7.5	7.5		CY	TOPSOIL	651.35	EST.			
150	150		SY	TEMPORARY EROSION MATTING	653.20	EST.			
1610	1610		SF	TRAFFIC SIGNS, TYPE A	675.20	0.84			
4575	4575		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
166	166		EACH	REMOVING SIGNS	675.50	-			
1	1		EACH	ERECTING SALVAGED SIGNS	675.60	-			
2	2		EACH	FLASHING BEACON, AERIAL MOUNTED	678.17	-			
34	34		EACH	SPECIAL PROVISION (18 INCH X 12 INCH OPTICAL SPEED BAR)	900.620	-			
52	52		EACH	SPECIAL PROVISION (DELINEATOR WITH STEEL POST)	900.620	-			

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
QUANTITY SHEET

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 5 OF 54