STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET – TOWN TOTALS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							BERKSHIRE TOTAL TSS SHEETS	303.66		11			37	10	31	56		840											
							CAMBRIDGE TOTAL TSS SHEETS	160.00		1			7	1	8	31		465											
							CHARLOTTE TOTAL TSS SHEETS	359.21					59		45	67		1005											
							FAIRFIELD TOTAL TSS SHEETS	156.18					13		12	29		435											
							FERRISBURGH TOTAL TSS SHEETS	60.36		1			7	1	7	11		165											
							HINESBURG CHARLOTTE RD TOTAL TSS SHEETS	257.50					21		21	53		795											
							HINESBURG HOLLOW RD TOTAL TSS SHEETS	134.25			1	1	9		9	25		375											
							HYDE PARK TOTAL TSS SHEETS	57.75					2		2	10		150											
							MIDDLESEX TOTAL TSS SHEETS	120.25					11		8	23		345											
										EA 13	EA 1	EA 1	EA 166	EA 12	EA 143		FT	FT 4575	FT		LB	LB	LB	LB					
							PROJECT GRAND TOTALS	SF 1609.16	SF	EA 181				EA 155		EA 305	FT 4575			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(9)

FILE NAME: dl0k318_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
TOWN TOTAL TRAFFIC SIGN SUMMARY

PLOT DATE: 22-OCT-2012
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 49 OF 54