STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - DUMMERSTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM ~~0.060~~ 0.081, RT	A	R2-1	24	30		SPEED LIMIT 35			~~X~~	X	X	X	~~X~~	X	1		13.5' X								RETAIN EXISTING SIGN AND POST ~~320~~ 210 FT NORTH OF THE INTERSECTION OF US-5			
NB	MM 0.060 RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS OVER WEIGHT PERMIT REQ'D	5.00		~~X~~	X	X	X			1		13.5' X								REPLACE ~~RETAIN~~ EXISTING SIGN ~~320~~ 100 FT NORTH OF THE INTERSECTION OF US-5 OVERWEIGHT PERMIT SIGN WAS SALVAGED ONTO THE NEW POST.		5	
SB	MM 0.130, LT	F	W3-1	30	30			6.25					X		X	1		13.5' X								REMOVE EXISTING STOP AHEAD SIGN AND REPLACE WITH NEW STOP AHEAD SYMBOL SIGN 690 FT NORTH OF THE INTERSECTION OF US-5	X		
NB	MM 0.132, RT	A	W11-1	30	30					X				X												RETAIN EXISTING SIGN AND POST 700 FT NORTH OF THE INTERSECTION OF US-5			
		A	W16-1P	18	24		SHARE THE ROAD			X																RETAIN EXISTING SIGN 700 FT NORTH OF THE INTERSECTION OF US-5			
NB	MM 0.483, RT	A	W1-10L	30	30								X		X											REMOVE EXISTING SIGN AND POST 11 FT NORTH OF POLE #31/GMP/41			
NB	MM ~~0.530~~ 0.501, RT	A	~~W1-1McL~~ W1-1McL	36	36			9.00								2		15' X 16'								INSTALL NEW SIGN ON 2 POSTS ~~145~~ 10 FT ~~NORTH~~ SOUTH OF POLE #2/3/48281		7	
		A	W13-1P	18	18		20 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1McL SIGN ON THE LEFT HAND POST	X		
NB	MM 0.575, RT	C	W1-6R	48	24			8.00					X		X	2		12' X 12'								INSTALL NEW SIGN ON 2 POSTS 15 FT NORTH OF POLE #48279	X		
NB	MM 0.583, RT	D	R1-1	30	30		STOP	6.25					X		X	1		12.5' X								INSTALL NEW SIGN AND POST ON THE NORTH SIDE OF HOUGHTON ROAD	X		
NB	MM 0.585, RT	D	R1-1	30	30		STOP	6.25					X		X	1		12.5' X								INSTALL NEW SIGN AND POST NORTHWEST SIDE OF NOURSE HOLLOW ROAD	X		
NB	MM 0.590, RT	A	W1-6L	48	24			8.00								2		12' X 12'								INSTALL NEW SIGN ON 2 POSTS 160 FT SOUTH AND ACROSS FROM POLE #GMP/1/NET/12-4/13	X		
SB	MM 0.622, LT	F	W1-1McR ~~W1-1MbR~~	36	36			9.00								2		14' X 14.5'								INSTALL NEW SIGN ON 2 POSTS 25 FT NORTH OF POLE #GMP/1/NET/12-4/13		7	
		F	W13-1P	18	18		20 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1MbR SIGN ON THE LEFT HAND POST	X		
NB	MM 0.810, RT	A	W1-1R	30	30			6.25								1		15.5' X								INSTALL NEW SIGN AND POST ~~50~~ 80 FT ~~NORTH~~ SOUTH OF POLE #17	X		
		A	W13-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1R SIGN ON THE SAME POST	X		
										EA ~~4~~ 2	EA 2	EA 2	EA ~~2~~ 7	EA ~~2~~ 1	EA ~~2~~ 6		FT	FT ~~180~~ 188.5	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF ~~65.75~~ 70.75	SF	EA 6				EA ~~4~~ 7		EA ~~12~~ 14	FT		~~180~~ 188.5	EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
DUMMERSTON TRAFFIC SIGN SUMMARY 1

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 8 OF 38

M.W.H. 11-21-2012