STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 - DUMMERSTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 2.050, LT	E	WI-6L	48	24			8.00								2		12′ X 12.5′									INSTALL NEW SIGN ON 2 POSTS 16 FT SOUTH OF AND ACROSS FROM POLE #4337/8T/26	X		
SB	MM 2.061, LT	F	WI-6R	48	24			8.00								2		12′ X 12.5′									INSTALL NEW SIGN ON 2 POSTS 42 FT NORTH OF AND ACROSS FROM POLE #433/7/8T/26	X		
SB	MM 2.084, LT	F	WI-2L	30	30			6.25								1		13′ X									INSTALL NEW SIGN AND POST 69 FT SOUTH OF AND ACROSS FROM POLE #433/8	X		
SB	MM 2.317, LT	F	W7-1	30	30			6.25								1		13′ X									205′ SOUTH OF AND INSTALL NEW SIGN AND POST ACROSS FROM POLE #17-1/20/433/13	X		
NB	MM 2.653, RT	A	R2-5	24	30								X		X												REMOVE EXISTING SIGN AND POST 1774 FT NORTH OF POLE #17-1/20/433/13			
NB	MM 2.720, RT	A	W3-5	36	36			9.00								2		13′ X 13.5′									INSTALL NEW SIGN ON 2 POSTS 2128 FT NORTH OF POLE #17-1/20/433/13	X		
NB	MM 2.835, RT	A	R2-1	24	30			5.00					X		X	1		13′ X									REPLACE EXISTING SIGN AND POST 2735 FT NORTH OF POLE #17-1/20/433/13	X		
SB	MM 2.835, LT	F	R2-1	24	30			5.00					X		X	1		13.5′ X									REPLACE EXISTING SIGN AND POST 2735 FT NORTH OF AND ACROSS FROM POLE #17-1/20/433/13	X		
SB	MM 2.084 LT	F	WI-2L	36	36			9.00					X		X	2		13′ X 14.5′									THIS LARGER SIGN REPLACES THE SIGN ON SHEET #11 ABOVE. THE OLD SIGN WENT TO THE TOWN.			
NB	MM 1.999 RT	A	WI-2R	36	36			9.00					X		X	2		13.5′ X 14.5′									SEE NOTE ABOVE. THE OLD SIGN WAS ON SHEET #10.			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60
			EA	EA	EA	EA 3 ~~3~~ 5	EA	EA ~~3~~ 5			FT	FT ~~150~~ 183.5					LB
SHEET SUBTOTALS	SF 65.50 ~~47.50~~	SF	EA ~~3~~ 5				EA ~~3~~ 5		EA 14 ~~10~~		FT ~~150~~ 183.5		EA	LB			

M.W.H. 11-21-2012

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
DUMMERSTON TRAFFIC SIGN SUMMARY 4

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 11 OF 38