STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - HARTFORD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
~~NB~~	~~MM 0.349, RT~~	~~B~~	~~W1-6R~~	~~48~~	~~24~~								~~X~~		~~X~~ ~~X~~											REMOVE EXISTING SIGN AND POSTS ACROSS FROM POLE #16/10 MISSING			
NB	MM 0.349, RT	A B	W1-8L W1-8R	18 18	24 24			3.00 3.00								2 ~~1~~		13' X 13'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET ACROSS FROM POLE #16/10	X		
NB	MM 0.359, RT	D	R1-1	30	30		STOP PAULA STREET	6.25			X	X	X X		X	1		13' X								REPLACE EXISTING SIGN AND POST FOR PAULA STREET	X		
SB	MM 0.394, LT	F	W1-3R	30	30			6.25								1		15' X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #GMP/12/NET/18 POLE #55208	X		
SB	MM 0.437, LT	H	R1-1	30	30		STOP TRUELL RD	6.25			X	X	X X		X	1		13.5' X								REPLACE EXISTING SIGN AND POST FOR TRUELL ROAD	X		
NB	MM ~~0.513,~~ 0.424 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		14' X								INSTALL NEW SIGN AND POST 70 FT ~~NORTH OF POLE #GMP/15/1~~ SOUTH OF TRUELL RD STOP SIGN	X		
SB	MM ~~0.513,~~ 0.426 LT	F	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		15' X								INSTALL NEW SIGN AND PST ~~70~~ 60 FT ~~NORTH AND ACROSS FROM POLE #GMP/15/1~~ SOUTH OF TRUELL RD STOP SIGN	X		
NB	MM 0.565, RT	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						X		X											REMOVE EXISTING SIGN AND POST 80 FT SOUTH OF POLE #GMP/17/23			
SB	MM 0.580, LT	F	W3-5	36	36		SPEED LIMIT 25 SEE BELOW	9.00								2		14' X 14.5'		SEE NOTE BELOW.						INSTALL NEW SIGN ON 2 POSTS 100 FT SOUTH OF POLE #3-8/24/GMP/18 POLE #55197	X		
NB	MM 0.602, RT	A	S3-1	36	36	F-Y-G		9.00								2		14' X 14.5'								INSTALL NEW SIGN ON 2 POSTS 20 FT NORTH AND ACROSS FROM POLE #3-8/24/GMP/18 POLE #55197	X		
NB	MM 0.630, RT	A A	W1-2R VW-060	30 30	30 30		HIDDED DRIVE RIGHT	6.25 6.25					X		X	2 ~~1~~		16.5' X 16.5'		CURVE SIGN ON TOP. HDR SIGN ON BOTTOM.						INSTALL NEW SIGN AND POST ACROSS FROM POLE #GMP/19 POLE #55193	X		
SB	MM 0.680, LT	F	W7-1	30	30			6.25								1		12.5' X								INSTALL NEW SIGN AND POST 30 FT NORTH OF POLE #28/~~20~~ 22	X		
SB	MM 0.557 LT	F	W3-5	36	36		SPEED LIMIT 25			X	X		X		X	2		14' X 14'		DUE TO A PROPERTY OWNER COMPLAINT, THIS SIGN WAS MOVED 120' FROM ORIGINAL LOCATION.									
																				45' N. OF POLE #GMP/19/55193									
							SHEET SUBTOTALS	SF 71.50 ~~65.25~~	SF	EA 1 3 2 ~~4~~ 8				EA ~~5~~ 6		EA ~~12~~ 16	FT ~~180~~ 227			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HARTFORD TRAFFIC SIGN SUMMARY 2

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 14 OF 38

M.W.H. 11-21-2012