STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 – PUTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.713, LT	F E	WI-8L WI-8R	18	24			3.00 3.00								2 +		12′ X 12′								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET 100~~ 125 FT SOUTH OF POLE #75/7-3>7/7I SEPARATE POSTS	X		
SB	MM 0.722, LT	H	RI-2	30	30								X		X											REMOVE EXISTING SIGN AND POST 53 FT SOUTH OF POLE #75/7-3>7/7I			
SB	MM 0.722, LT	H	RI-1	30	30		STOP AIKEN RD WEST HILL	6.25			X X	X X	X X			1		13.5′ X		STREET SIGNS WERE SALVAGED ONTO THE NEW POST.						INSTALL NEW SIGN AND POST 53 FT SOUTH OF POLE #75/7-3>7/7I	X		
SB	MM 0.740, LT	F E	WI-8L WI-8R	18	24			3.00 3.00								2 +		12′ X 12′								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 42 FT ~~NORTH~~ SOUTH OF POLE #75/7-3>7/7I SEPARATE POSTS	X		
SB	MM 0.760, LT	F	WI-1McL	36	36			9.00								2		14.5′ X 14.5′								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE #GMP/74		7	
		F	WI3-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-1McL SIGN ON THE LEFT HAND POST	X		
NB	MM 0.890, RT	A	WI-5R	30	30			6.25								1		14′ X								INSTALL NEW SIGN AND POST 53 FT SOUTH OF AND ACROSS FROM POLE #7/65	X		
		A	WI3-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-5R SIGN ON THE SAME POST	X		
SB	MM 1.120, LT	F	WI-5R	30	30			6.25								1		15.5′ X								INSTALL NEW SIGN AND POST ~~ADJACENT TO~~ ACROSS FROM POLE #6I/17733/7/56	X		
		F	WI3-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAUQUE BELOW WI-5R SIGN ON THE SAME POST	X		
NB	MM 1.142, RT	A	WI-1MaL	36	36			9.00								2		14′ X 15′								INSTALL NEW SIGN ON 2 POSTS 30 FT SOUTH OF POLE #7/55/17732		7	
		A	WI3-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-1McL SIGN ON THE LEFT HAND POST	X		
SB	MM 1.160, LT	F	TOWN SIGN	30	30		WATCH FOR CHILDREN AT PLAY						X		X											REMOVE EXISTING SIGN AND POST 74 FT SOUTH OF AND ACROSS FROM POLE #V 254/58/109853			
NB	MM 1.174, RT	B	WI-6R	48	24			8.00								2		12′ X 12.5′								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE #V 254/58/109853	X		
NB	MM 1.174, RT	A	WI-6L	48	24			8.00								2		12′ X 12.5′								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE #V 254/58/109853	X		
SB	MM 1.196, LT	F	VW-054	24	30		HIDDEN DRIVE RIGHT						X		X											REMOVE EXISTING SIGN AND POST SOUTH OF AND ACROSS FROM POLE #V253/57/109850			
										EA	EA 2	EA 2	EA ~~3~~ 5	EA	EA 3		FT	FT ~~195~~ 198	FT		LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 73.75	SF	EA 3				EA 3		EA ~~13~~ 15	FT ~~195~~ 198			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PUTNEY TRAFFIC SIGN SUMMARY 2

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 17 OF 38

M.W.H. 11-21-2012