STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - PUTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL IN SHS	SIGN DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.196, LT	F	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1		14′ X								INSTALL NEW SIGN AND POST SOUTH OF AND ACROSS FROM POLE #V253/57/109850		7	
NB	MM 1.198, RT	C	R2-5	24	30		~~REDUCED SPEED AHEAD~~ SPEED ZONE AHEAD			X			~~X~~	X	~~X~~						SIGN WAS ACTUALLY ON HOUGHTON BROOK RD.					REMOVE EXISTING SIGN AND POST ADJACENT TO POLE #V253/57/109850			
~~NB~~	~~MM 1.198, RT~~	~~C~~	~~W3-5~~	~~36~~	~~36~~		~~SPEED LIMIT 35~~	0.00 ~~9.00~~								~~2~~		~~X~~			THIS SIGN WAS NOT INSTALLED. NO SPEED REDUCTION HERE.					INSTALL NEW SIGN ON 2 POSTS AT ADJACENT TO POLE #V253/57/109850	X		
NB	MM 1.206, RT	D	RI-1	30	30		STOP	6.25					X		X	1		12.5′ X								REPLACE EXISTING SIGN AND POST AT NORTHEAST CORNER OF HOUGHTON BROOK ROAD AND WEST HILL ROAD INTERSECTION	X		
NB	MM 1.244, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		13.5′ X								REPLACE EXISTING SIGN AND POST 16 FT SOUTH OF POLE #55/7/51/17726	X		
SB	MM 1.244, LT	F	WI-IR	30	30			6.25								1		15′ X								INSTALL NEW SIGN AND POST 16 FT SOUTH OF AND ACROSS FROM POLE #55/7/51/17726	X		
		F	WI3-IP	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-IR SIGN ON THE SAME POST	X		
NB	MM 1.400, RT	A	WI-IR	30	30			6.25								1		15′ X								INSTALL NEW SIGN AND POST ~~HFT~~ 150 SOUTH OF POLE #48/7/44/17603	X		
		A	WI3-IP	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-IR SIGN ON THE SAME POST	X		
SB	MM 1.445, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		12.5′ X								REPLACE EXISTING SIGN AND POST 127 FT NORTH OF AND ACROSS FROM POLE #48/7/44/17603	X		
NB	MM 1.484, RT	A	TOWN SIGN	24	24		BLIND DRIVE						X		X											REMOVE EXISTING SIGN AND POST 338 FT SOUTH OF POLE #39/17594			
NB	MM 1.484, RT	A	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1		13′ X								INSTALL NEW SIGN AND POST 338 FT SOUTH OF POLE #39/17594		7	
SB	MM 1.484, LT	F	VW-133	30	30		HIDDEN DRIVE LEFT	6.25								1		13′ X								INSTALL NEW SIGN AND POST 229 FT SOUTH OF AND ACROSS FROM POLE #39/17594		7	
SB	MM 1.548, LT	F	WI-IMfL	36	36			9.00								2		16′ X 17′								65′ NORTH OF AND ACROSS FROM INSTALL NEW SIGN ON 2 POSTS ~~ACROSS FROM~~ POLE #39/17594		7	
		F	WI3-IP	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW WI-IMfL SIGN ON THE LEFT HAND POST	X		
NB	MM 1.980, RT	A	W7-1	30	30			6.25					X		X	1		15′ X								REPLACE EXISTING SIGN AND POST 74 FT SOUTH OF AND ACROSS FROM POLE #7/21/GMP/25	X		
										EA	EA	EA	EA ~~6~~ 5	EA	EA 6			FT ~~180~~ 156.5					LB	LB	LB	LB					
							SHEET SUBTOTALS	SF ~~78.50~~ 69.50	SF	EA ~~6~~ 5				EA 6		EA 13		FT ~~195~~ 156.5		EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PUTNEY TRAFFIC SIGN SUMMARY 3

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 18 OF 38

M.W.H. 11-21-2012