STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 – PUTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 2.013, RT	A	W1-5L	30	30			6.25					X		X	1		15′ X								REPLACE EXISTING SIGN AND POST 21 FT SOUTH OF POLE #GMP/24 POLE #17571	X		
		A	W13-1P	18	18			2.25																		INSTALL NEW PLAQUE BELOW W1-5L SIGN ON THE SAME POST	X		
NB	MM 2.069, RT	A B	W1-8L W1-8R	18	24			3.00 3.00								2 +		8′ X 12′								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 79 FT SOUTH OF POLE #18/GMP/18 SEPARATE POSTS	X		
NB	MM 2.084, RT	A B	W1-8L W1-8R	18	24			3.00 3.00								2 +		12′ X 12′								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ ADJACENT TO POLE #18/GMP/18 SEPARATE POSTS	X		
SB	MM 2.124, LT	F	TOWN SIGN	24	24								X		X											REMOVE EXISTING SIGN AND POST ACROSS FROM POLE #17/GMP/17			
SB	MM 2.124, LT	F	VW-054 ~~VW-081~~	30	30			6.25								1		15′ X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #17/GMP/17		7	
SB	MM 2.130, LT TO MM 2.223, LT	F E		6	8		(18) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS BACK-TO-BACK 60 FT APART ON 9 POSTS, INSTALL THE FIRST SET 32 FT NORTH OF AND ACROSS FROM POLE #17/GMP/17		6	
NB	MM 2.291, RT	A	W1-1L	30	30			6.25					X		X	1		15.5′ X								REPLACE EXISTING SIGN AND POST 322 FT NORTH OF AND ACROSS FROM POLE #17565	X		
		A	W13-1P	18	18			2.25																		INSTALL NEW PLAQUE BELOW W1-1L SIGN ON THE SAME POST	X		
SB	MM 2.393, LT	F	W1-1R	30	30			6.25								1		15′ X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #GMP/8/8 POLE #17558	X		
		F	W13-1P	18	18			2.25																		INSTALL NEW PLAQUE BELOW W1-1R SIGN ON THE SAME POST	X		
SB	MM 2.410, LT	F	W1-2R	30	30								X		X											REMOVE EXISTING SIGN AND POST 243 FT SOUTH OF AND ACROSS FROM POLE #GMP/6 POLE #17556			
SB	MM 2.456, LT	F	W1-5R	30	30			6.25								1		15′ X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #GMP/6 POLE #17556	X		
		F	W13-1P	18	18			2.25																		INSTALL NEW PLAQUE BELOW W1-5R SIGN ON THE SAME POST	X		
NB	MM 2.547, RT	A	W3-1	30	30			6.25								1		14′ X								INSTALL NEW SIGN AND POST 69 FT NORTH OF POLE #GMP/3	X		
SB	MM 2.570, LT	H	R1-1	30	30			6.25					X		X	1		12′ X								REPLACE EXISTING SIGN AND POST 25 FT FROM THE SOUTHWEST CORNER OF CROSS ROAD AND WEST HILL ROAD INTERSECTION	X		
										EA	EA	EA	EA 5	EA	EA 5		FT	FT ~~135~~ 145.5	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 64.75	SF	EA 5				EA 5		EA ~~9~~ 11	FT ~~135~~ 145.5			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PUTNEY TRAFFIC SIGN SUMMARY 4
PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 19 OF 38

M.W.H. 11-21-2012