STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 5 – PUTNEY

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) 1.75 lb/ft 1.88 | SQUARE STEEL (in) 2.00 lb/ft 2.42 | SQUARE STEEL (in) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(in) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(in) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(in) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHS = STANDARD HIGHWAY SIGN BOOK | SIGN DETAIL DETAIL IN SHS | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SB | MM 2.600, LT | F | W1-5R | 36 | 36 | | | | | | | | X | | X | | | | | | | | | | | REMOVE EXISTING SIGN AND POST ADJACENT TO POLE #GMP/1 | | | |
| | | F | R2-1 | 24 | 30 | | | | | | | | X | | | | | | | | | | | | | REMOVE EXISTING SIGN ADJACENT TO POLE #GMP/1 | | | |
| | | F | VR-017 | 24 | 30 | | | | | | | | X | | | | | | | | | | | | | REMOVE EXISTING SIGN ADJACENT TO POLE #GMP/1 | | | |
| SB | MM 2.600, LT | F | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | 15' X | | | | | | | | INSTALL NEW SIGN AND POST ADJACENT TO POLE #GMP/1 | X | | |
| | | F | R12-1 | 24 | 30 | | LLL 24,000 POUNDS | 5.00 | | | | | | | | | | | | | | | | | | INSTALL NEW SIGN BELOW R2-1 SIGN ON THE SAME POST | X | | |
| NB | MM 2.620, RT | A | R1-1 | 30 | 30 | | | 6.25 | | | | | X | | X | 1 | | 12.5' X | | | | | | | | REPLACE EXISTING SIGN AND POST NORTH OF AND ACROSS FROM POLE #GMP/1 | X | | |
| SB | MM 2.620, LT | E | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 13' X | | | | | | | | INSTALL NEW SIGN AND POST NORTH OF POLE #GMP/1 AND ACROSS FROM EXISTING STOP SIGN | X | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| NB | 1.198 RT | | R2-1 | 24 | 30 | | SPEED LIMIT 25 | 5.00 | | | | | X | | | 1 | | 12.5' X | | | | | | | | SIGN INSTALLED ON HOUGHTON BROOK RD. | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SB | 0.30 ~ 0.65 LT | | | 6 | 8 | | 25 TYPE II 6" x 8" WHITE DELINEATORS. ONE PER POST FACING MOTORISTS IN THE SB LANE SHOULDER. | | | | | | | | | | | | | | | | | | | NEW DELINEATORS INSTALLED ON SIDE FACING MOTORISTS (SINGLE) AT 50' SPACING AS REQUESTED BY TOWN ROAD FORMAN. SEE ALSO SHEET #36 | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | **SHEET SUBTOTALS** | SF ~~22.50~~ 27.50 | SF | EA 4 | | | | EA 2 | | EA 3 | FT ~~45~~ 53.0 | | | EA | LB | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

| | |
|---|---|
| PROJECT NAME: | STATEWIDE SOUTHEAST REGION |
| PROJECT NUMBER: | STP HRRR(10) |
| FILE NAME: d10k320_wrk.dgn | PLOT DATE: 09-AUG-2011 |
| PROJECT LEADER: JLS | DRAWN BY: ITS |
| DESIGNED BY: NLA | CHECKED BY: JLS |
| PUTNEY TRAFFIC SIGN SUMMARY 5 | SHEET 20 OF 38 |

M.W.H. 11-21-2012