STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - SPRINGFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.000, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00								1		11.5′ X								INSTALL NEW SIGN AND POST 48 FT SOUTH FROM AUSTIN ROAD	X		
NB	MM 0.000, RT	C	VD-024	72	10		Springfield | Rockingham	5.00								2		12′ X 12′								INSTALL NEW SIGN ON 2 POSTS ADJACENT TO R2-1SIGN AND 48 FT SOUTH FROM AUSTIN ROAD		7	
NB	MM 0.000, RT	C	VD-024	72	10		Windsor Co. | Windham Co.	5.00																		INSTALL NEW SIGN BELOW VD-024 SIGN ON THE SAME 2 POSTS		7	
SB	MM 0.000, LT	F	R2-5	24	30		REDUCED SPEED AHEAD						X		X											REMOVE EXISTING SIGN AND POST 48 FT SOUTH OF AND ACROSS FROM AUSTIN ROAD			
SB	MM 0.000, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00								1		12.5′ X								INSTALL NEW SIGN AND POST 48 FT SOUTH OF AND ACROSS FROM AUSTIN ROAD	X		
NB	MM 0.009, RT	C	R1-1	30	30		STOP	6.25								1		12.5′ X								INSTALL NEW SIGN AND POST 47 FT SOUTH OF POLE *CTC 129	X		
NB	MM 0.040, RT	A	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE EXISTING SIGN AND POST 116 FT NORTH OF POLE *CTC 129			
NB	MM 0.040, RT	A	W1-5R	30	30			6.25								1		14′ X								INSTALL NEW SIGN AND POST 116 FT NORTH OF POLE *CTC 129	X		
		A	W7-3aP	24	18		NEXT 1 MILE	3.00																		INSTALL NEW PLAQUE BELOW W1-5R SIGN ON THE SAME POST	X		
NB	MM 0.401, RT	A	W1-1R	30	30			6.25								1		14.5′ X								INSTALL NEW SIGN AND POST ADJACENT TO POLE *VTEL 4	X		
		A	W13-1P	18	18		15 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1R SIGN ON THE SAME POST	X		
SB	MM 0.431, LT	F E	W1-8R W1-8L	18 18	24 24			3.00 3.00								1+1 2		11′ X 11.5′								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 249 FT SOUTH OF POLE *CTC VT35/6 SEPARATE POSTS	X		
SB	MM 0.446 SB	F E	W1-8R W1-8L	18 18	24 24			3.00 3.00								1+1 2		9′ X 9′								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 169 FT SOUTH OF POLE *CTC VT35/6 SEPARATE POSTS	X		
SB	MM 0.461 SB	F E	W1-8R W1-8L	18 18	24 24			3.00 3.00								1+1 2		11′ X 11′								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 89 FT SOUTH OF POLE *CTC VT35/6 SEPARATE POSTS	X		
SB	MM 0.488, LT	F	W1-1L	30	30			6.25								1		16′ X								INSTALL NEW SIGN AND POST 53 FT NORTH OF POLE *CTC VT35/6	X		
		F	W13-1P	18	18		15 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1L ON THE SAME POST	X		
										EA	EA	EA	EA 2	EA	EA 2		FT	FT ~~165~~ 167.5	FT					LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 70.50	SF	EA 2				EA 2		EA ~~11~~ 13	FT	FT ~~165~~ 167.5		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

M.W.H. 11-21-2012

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
SPRINGFIELD TRAFFIC SIGN SUMMARY 1

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 22 OF 38