STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - SPRINGFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.605, RT	D	RI-1	30	30		STOP	6.25					X		X	1		13' X								REPLACE EXISITING SIGN AND POST 153 FT NORTH OF POLE #CTC VT/35/9. UPSIZE FROM 24" TO 30".	X		
NB	MM 1.008, RT	A	W1-3L	30	30			6.25								1		16.5' X								INSTALL NEW SIGN AND POST 1120 FT NORTH OF AND ACROSS FROM MAILBOX #1019	X		
SB	MM 1.140, LT	F	W1-3L	30	30			6.25								1		12' X								INSTALL NEW SIGN AND POST 1816 FT NORTH OF MAILBOX #1019	X		
NB	MM 1.170, RT	A	VS3-4A	30	30		SCHOOL BUS TURN AROUND AHEAD						X		X											REMOVE EXISTING SIGN AND POST 375 FT SOUTH OF AND ACROSS FROM FOX CHAIR MTN ROAD			
NB	MM 1.188, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		12.5' X								INSTALL NEW SIGN AND POST 280 FT SOUTH OF AND ACROSS FROM FOX CHAIR MTN ROAD	X		
SB	MM 1.188, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00								1		14.5' X								INSTALL NEW SIGN AND POST 280 FT SOUTH OF FOX CHAIR MTN ROAD	X		
NB	MM 1.216, RT	A	S3-2	36	36	F-Y-G	SCHOOL BUS TURN AHEAD	9.00								2		16.5' X 17.5'								INSTALL NEW SIGN ON 2 POSTS 132 FT SOUTH OF AND ACROSS FROM FOX CHAIR MTN ROAD	X		
		A	W1-10R	36	36			9.00																		INSTALL NEW SIGN BELOW S3-2 SIGN ON THE SAME 2 POSTS	X		
		A	W16-8P	36 ~~30~~	8		Boedtker Rd	2.00 ~~1.67~~																		INSTALL NEW PLAQUE BELOW W1-10R SIGN ON THE SAME 2 POSTS		7	
SB	MM 1.216, LT	F	W1-5R	30	30			6.25								1		15.5' X								INSTALL NEW SIGN AND POST 132 FT SOUTH OF FOX CHAIR MTN ROAD	X		
		F	W7-3aP	24	18		NEXT 1 MILE	3.00																		INSTALL NEW PLAQUE BELOW W1-5R ON THE SAME POST	X		
SB	MM 1.234, LT	H	RI-1	30	30		STOP	6.25					X		X	1		12.5' X								INSTALL NEW SIGN AND POST 300 FT FROM THE SOUTHWEST CORNER OF FOX CHAIR MTN ROAD AND PLEASANT VALLEY ROAD INTERSECTION	X		
NB	MM 1.265, RT	D	RI-1	30	30		STOP	6.25								1		12.5' X								INSTALL NEW SIGN AND POST 127 FT NORTH OF AND ACROSS FROM FOX CHAIR MOUNTAIN ROAD	X		
NB	MM 1.265, RT	C	RI-1	30	30		STOP	6.25								1		12.5' X								INSTALL NEW SIGN AND POST SOUTH OF BOEDTKER ROAD AND ADJACENT TO DEAD END SIGN	X		
		C	W14-2	30	30		NO OUTLET	6.25								1		12.5' X								INSTALL NEW SIGN AND POST ON RIGHT SIDE OF BOEDTKER JUST AFTER INTERSECTION ACROSS FROM REMOVED DEAD END SIGN ASSEMBLY	X		
NB	MM 1.283, RT	D	RI-1	30	30		STOP	6.25					X		X	1		12.5' X								INSTALL NEW SIGN AND POST ADJACENT TO POLE #CVPS 15T/3521/3/13	X		
										EA	EA	EA	EA ~~2~~ 5	EA	EA 2		FT	FT ~~195~~ 180.5	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF ~~88.92~~ 89.25	SF	EA 2				EA 2		EA 13	FT ~~195~~ 180.5			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
SPRINGFIELD TRAFFIC SIGN SUMMARY 2

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 23 OF 38

M.W.H. 11-21-2012