STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - SPRINGFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.283, RT	C	W14-1	30	30		DEAD END						~~X~~		~~X~~											REMOVE EXISTING SIGN AND POST NORTH OF BOEDTKER ROAD MISSING			
SB	MM 1.297, LT	H	R1-1	30	30		STOP	6.25								1		12' X								INSTALL NEW SIGN AND POST AT THE NORTHWEST CORNER OF WHITNEY ROAD AND PLEASANT VALLEY ROAD INTERSECTION	X		
NB	MM 1.305, RT	A	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE EXISTING SIGN AND POST 42 FT NORTH OF AND ACROSS FROM WHITNEY ROAD			
		A	TOWN SIGN	12	18		NO OVERNIGHT PARKING						X													REMOVE EXISTING SIGN 42 FT NORTH OF AND ACROSS FROM WHITNEY ROAD			
NB	MM 1.305, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		12.5' X								INSTALL NEW SIGN AND POST 42 FT NORTH OF AND ACROSS FROM WHITNEY ROAD	X		
SB	MM 1.319, LT	F	VS3-4A	30	30		SCHOOL BUS TURN AROUND AHEAD						X		X											REMOVE EXISTING SIGN AND POST 116 FT NORTH OF WHITNEY ROAD			
SB	MM 1.319, LT	F	S3-2	36	36	F-Y-G	SCHOOL BUS TURN AHEAD	9.00								2		14' X 14.5'								INSTALL NEW SIGN ON 2 POSTS 116 FT NORTH OF WHITNEY ROAD	X		
SB	MM 1.340, LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SIGN AND POST 227 FT NORTH OF WHITNEY ROAD			
NB	MM 1.590, RT	A	W1-1R	30	30			6.25								1		13.5' X								INSTALL NEW SIGN AND POST 1515 FT SOUTH OF RUUSUNEN ROAD	X		
		A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1R SIGN ON THE SAME POST	X		
SB	MM 1.610, LT	F E	W1-8L W1-8R	18 18	24 24			3.00 3.00								2 +		12' X 12'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 1410 FT SOUTH OF AND ACROSS FROM RUUSUNEN ROAD SEPARATE POSTS	X		
SB	MM 1.625, LT	F E	W1-8L W1-8R	18 18	24 24			3.00 3.00								2 +		12' X 12'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 1330 FT SOUTH OF AND ACROSS FROM RUUSUNEN ROAD SEPARATE POSTS	X		
SB	MM 1.640, LT	F E	W1-8L W1-8R	18 18	24 24			3.00 3.00								2 +		12' X 12'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 1330 FT SOUTH OF AND ACROSS FROM RUUSUNEN ROAD SEPARATE POSTS	X		
SB	MM 1.661, LT	F	W1-1L	30	30			6.25								1		17' X								INSTALL NEW SIGN AND POST 1140 FT SOUTH OF AND ACROSS FROM RUUSUNEN ROAD	X		
		F	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1L SIGN ON THE SAME POST	X		
NB	MM 1.872, RT	C	W14-1	30	30		DEAD END						X		X											REMOVE EXISTING SIGN AND POST SOUTH OF RUUSUNEN ROAD			
										EA	EA	EA	EA ~~6~~ 5	EA	EA 5													
							SHEET SUBTOTALS	SF 55.25	SF	EA ~~6~~ 5				EA 5		EA ~~9~~ 12													
																	FT	FT ~~135~~ 155.5	FT		LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
SPRINGFIELD TRAFFIC SIGN SUMMARY 3

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 24 OF 38

M.W.H. 11-21-2012