STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 - SPRINGFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 1.872, RT	C	W14-2	30	30		NO OUTLET	6.25								1		12.5' X								INSTALL NEW SIGN AND POST SOUTH OF RUUSUNEN ROAD	X		
~~NB~~	~~MM 1.877, RT~~	~~C~~	~~R2-1~~	~~24~~	~~30~~		~~SPEED LIMIT 25~~						~~X~~		~~X~~											REMOVE EXISTING SIGN AND POST NORTH OF RUUSUNEN ROAD AND BACK-TO-BACK WITH STOP SIGN MISSING			
NB	MM 1.877, RT	D	R1-1	30	30		STOP	6.25					X		X	1		12.5' X								INSTALL NEW SIGN AND POST NORTH OF RUUSUNEN ROAD	X		
SB	MM 1.897, RT	H	R1-1	30	30		STOP	6.25					X		X	1		12.5' X								INSTALL NEW SIGN AND POST SOUTH OF POPPE ROAD	X		
NB	MM 2.010, RT	A	W1-1R	30	30			6.25								1		13.5' X								INSTALL NEW SIGN AND POST 392 FT SOUTH OF POLE #352/38/CV6T/VTC ~~#3~~ 13	X		
		A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1R ON THE SAME POST	X		
SB	MM 2.036, LT	F E	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								2 +		12' X 12'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET 128~~ 140 FT SOUTH OF AND ACROSS FROM POLE #352/38/CV6T/VTC ~~#3~~ 13 SEPARATE POSTS	X		
SB	MM 2.051, LT	F E	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								2 +		12' X 12'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET 48~~ 60 FT SOUTH OF AND ACROSS FROM POLE #352/38/CV6T/VTC ~~#3~~ 13 SEPARATE POSTS	X		
SB	MM 2.066, LT	F E	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								2 +		12' X 12'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET 32~~ 20 FT NORTH OF AND ACROSS FROM POLE #352/38/CV6T/VTC ~~#3~~ 13 SEPARATE POSTS	X		
SB	MM 2.082, LT	F	W1-1L	30	30			6.25								1		17' X								INSTALL NEW SIGN AND POST 116 FT NORTH OF AND ACROSS FROM POLE #352/38/CV6T/VTC ~~#3~~ 13	X		
		F	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1L SIGN ON THE SAME POST	X		
SB	MM 2.375, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		13' X								INSTALL NEW SIGN AND POST ~~ADJACENT TO~~ ACROSS FROM POLE #791/19	X		
NB	MM 2.396, RT	A	TOWN SIGN	30	30		SHARP CURVE AHEAD						X		X											REMOVE EXISTING SIGN AND POST 111 FT NORTH OF POLE #791/19			
NB	MM 2.429, RT	A	W1-1MdR	36	36			9.00								2		13' X 14'								INSTALL NEW SIGN ON 2 POSTS 285 FT NORTH OF POLE #791/19		7	
		A	W13-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1MdR SIGN ON THE LEFT HAND POST	X		
SB	MM 2.474, LT	F E	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								2 +		12.5' X 12.5'								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON ~~SIGN BRACKET~~ 90 FT SOUTH OF POLE #CTC 17/791/16 SEPARATE POSTS			
										EA	EA	EA	EA ~~2~~ 3	EA	EA 2		FT	FT ~~180~~ 205	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 76.00	SF	EA ~~2~~ 3				EA 2		EA ~~12~~ 16	FT ~~180~~ 205			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
SPRINGFIELD TRAFFIC SIGN SUMMARY 4

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 25 OF 38

M.W.H. 11-21-2012