STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6 - SPRINGFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 3.200, LT	F	VR-017	24	24		LEGAL LOAD LIMIT 24,000 POUNDS				X	X	X		X	1		13' X								REMOVE EXISTING SIGN AND POST 444 FT NORTH OF AND ACROSS FROM POLE #CTC/2			
SB	MM 3.200, LT	F	R12-1	24	30		~~WEIGHT LIMIT 3 TONS~~	0.00 ~~5.00~~								~~1~~		~~X~~			SIGN WAS REMOVED PRIOR TO THE PROJECT.					~~INSTALL NEW SIGN AND POST 444 FT NORTH OF AND ACROSS FROM POLE #CTC/2~~	~~X~~		
		F	R2-1	24	30		SPEED LIMIT 35 PLEASANT VALLEY RD	5.00			X	X	X							STREET SIGN WAS SALVAGED ONTO THE NEW POST INSTALLED ABOVE.						INSTALL NEW PLAQUE BELOW R12-1 ON THE SAME POST	X		
NB	MM 3.210, RT	A	R1-1	30	30		STOP	6.25					X		X	1		13' X								REPLACE EXISTING SIGN AND POST AT THE SOUTHEAST CORNER OF VT-11 AND PLEASANT VALLEY ROAD INTERSECTION	X		
NB	MM 0.200 RT	A	R1-1	30	30		STOP	6.25								1		11.5' X								AUSTIN RD			
NB	MM 0.605 RT	A	W14-2	30	30		NO OUTLET	6.25								1		13' X								LOVELL RD			
SB	MM 2.500 LT	H	R1-1	30	30		STOP	6.25								1		12.5' X								JOHNSON RD			
NB	MM 1.216 RT	A	W16-8P	42	8		FOX CHAIR MTN RD	2.33																		THIS SIGN WAS MISTAKENLY ORDERED BY THE R.E. IT WAS GIVEN TO THE TOWN AND THE BOEDTKER RD SIGN ON STREET #23 WAS ORDERED AND INSTALLED.			
								EA	EA	EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB					
									2	2	~~2~~ 3		2					~~30~~ 63											
							SHEET SUBTOTALS	SF ~~16.25~~ 32.33	SF	EA ~~2~~				EA 2		EA ~~2~~ 5	FT ~~30~~ 63			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
SPRINGFIELD TRAFFIC SIGN SUMMARY 6

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 27 OF 38

M.W.H. 11-21-2012