STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - THETFORD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 0.643, LT	F	WI-5L	30	30			6.25								1		15.5′ X								INSTALL NEW SIGN AND POST 425 FT EAST OF POLE #71-4	X		
		F	WI3-1P	18	18		20 MPH	2.25																		INSTALL NEW PLAQUE BELOW WI-5L SIGN ON THE SAME POST	X		
EB	MM 0.640, RT TO MM 0.840, RT	A B		6	8		38 ~~(34)~~ TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS 19 BACK-TO-BACK 60 FT APART ON ~~17~~ POSTS, INSTALL THE FIRST SET 630 FT WEST AND ACROSS FROM POLE #371/71-01		6	
EB	MM 1.150, RT	A		6	8		(1) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL ONE DELINEATOR 5 FT WEST OF POLE #9/790/27		6	
WB	MM 1.390, LT TO MM 1.570, LT	E F		6	8		(32) TYPE II - 6" X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS BACK-TO-BACK 60 FT APART ON 16 POSTS, INSTALL THE FIRST SET 40 FT EAST OF POLE #22/NET/4		6	
WB	MM 1.570, LT	H	RI-1	30	30		STOP	6.25					X		X	1		12.5′ X								REPLACE EXISTING SIGN AND POST AT THE SOUTHWEST SIDE OF TH #21	X		
EB	MM 1.625, RT	D	RI-1	30	30		STOP	6.25					X		X	1		13′ X								REPLACE EXISTING SIGN AND POST AT THE NORTHEAST SIDE OF THE COLBY ROAD (SOUTH)	X		
EB	MM 1.650, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		11.5′ X								REPLACE EXISTING SIGN AND POST 105 FT EAST OF POLE #1061/26			
EB	MM 1.770, RT	A	WI-2L	30	30			6.25								1		12′ X								INSTALL NEW SIGN AND POST 50 FT WEST AND ACROSS FROM POLE #23/NET/14	X		
EB	MM 1.844, RT	A	WI-6L	48	24			8.00								2		13′ X 13.5′								INSTALL NEW SIGN ON 2 POSTS 140 FT WEST OF POLE #15T/790/11/NET/1061	X		
EB	MM 1.844, RT	B	WI-6L	48	24			8.00								2		13.5′ X 14′								INSTALL NEW SIGN ON 2 POSTS 135 FT WEST OF POLE #15T/790/11/NET/1061	X		
EB	MM 1.865, RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SIGN AND POST			
WB	MM 1.880, LT	F	WI-2R	30	30			6.25								1		15′ X								INSTALL NEW SIGN AND POST 130 ~~80~~ FT EAST AND ACROSS FROM POLE #15T/790/11/NET/1061	X		
EB	MM 1.930, RT	A	W7-1	30	30			6.25								1		13′ X								INSTALL NEW SIGN AND POST 170 ~~120~~ FT WEST OF POLE #19/NET/9	X		
WB	MM 2.140, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		12′ X								REPLACE EXISTING SIGN AND POST 65 FT WEST OF POLE #15/NET/790/5	X		
EB	MM 2.420, RT	A	TOWN SIGN	12	18		SLOW CHILDREN						X		X											REMOVE EXISTING SIGN AND POST			
										EA	EA	EA	EA 6	EA	EA 6		FT	FT ~~180~~ 158.5	FT										
							SHEET SUBTOTALS	SF 65.75	SF	EA 6				EA 6		EA 12	FT	~~180~~ 158.5		EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
THETFORD TRAFFIC SIGN SUMMARY 2

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 30 OF 38

M.W.H. 11-21-2012