STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 – THETFORD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL IN SHS	SIGN DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 2.447, RT	A	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25					X		X	1		13.5′ X								REPLACE EXISTING SIGN AND POST 1020 FT WEST OF POLE ~~#165/5~~ 167		7	
EB	MM 2.630, RT	A	W1-1L	30	30			6.25								1		14′ X								INSTALL NEW SIGN AND POST 50 FT WEST OF POLE ~~#165/5~~ 167	X		
		A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1L SIGN ON THE SAME POST	X		
EB	MM 2.670, RT	A	W1-6L	48	24			8.00								2		10.5′ X 13′								INSTALL NEW SIGN ON 2 POSTS 155 FT EAST OF POLE ~~#165/5~~ 167	X		
EB	MM 2.670, RT	B	W1-6R	48	24			8.00								2		10.5′ X 13′								INSTALL NEW SIGN ON 2 POSTS 160 FT EAST OF POLE ~~#165/5~~ 167	X		
WB	MM 2.685, LT	F	TOWN SIGN	12	18		SLOW CHILDREN						X		X											REMOVE EXISTING SIGN AND POST			
WB	MM 2.700, LT	F	W1-1R	30	30			6.25								1		15′ X								INSTALL NEW SIGN AND POST 380 FT WEST AND ACROSS FROM POLE #1061/1/25T	X		
		F	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-1R SIGN ON THE SAME POST	X		
EB	MM 2.770, RT	A	W3-1	30	30			6.25								1		12′ X								INSTALL NEW SIGN AND POST 15 FT WEST OF POLE #1061/1/25T	X		
WB	MM 2.815, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		17′ X								REPLACE EXISTING SIGN AND POST 75 FT WEST OF THE INTERSECTION WITH VT-113	X		
		F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X													REPLACE EXISTING SIGN BELOW R2-1 (SL-35) SIGN ON THE SAME POST	X		
EB	MM 2.825, RT	A	R1-1	30	30		STOP 1130 0911 0358	6.25			X	X	X X		X	1		13.5′ X								REPLACE EXISTING SIGN AND POST AT MP 3.585 OF VT-113, SALV. MILE MARKER	X		
EB	MM 0.21 RT TO MM 0.64 RT			6	8		50 TYPE II - 6" x 8" WHITE DELINEATORS - 40′ SPACING															INSTALL 50 DELINEATORS ON NEW POSTS (SINGLE DELINEATOR), FACING MOTORISTS IN EB LANE ALONG BROOK AS REQUESTED BY TOWN ROAD FOREMAN. SEE ALSO SHEET #36.			
							BARKER ~~BAKER ROAD~~																							
NB	MM 0.020, RT	A	R2-1	24	30		SPEED LIMIT 30	5.00								1		14′ X								INSTALL NEW SIGN AND POST 105 FT NORTH THE INTERSECTION OF SAWNEE BEAN ROAD	X		
NB	MM 0.052, RT	A	R2-1	24	30		SPEED LIMIT 30						X		X											REMOVE EXISTING SIGN AND POST 40 FT NORTH OF PHELPS ROAD			
										EA	EA 1	EA 1	EA ~~6~~ 7	EA	EA 5			FT	FT ~~165~~ 146	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 66.75	SF	EA ~~6~~				EA 5		EA 11		FT	~~165~~ 146		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(10)

FILE NAME: d10k320_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
THETFORD TRAFFIC SIGN SUMMARY 3

PLOT DATE: 09-AUG-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 31 OF 38