STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - ARLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) lb/ft 1.75 / 1.88	SQUARE STEEL (in) lb/ft 2.00 / 2.42	SQUARE STEEL (in) lb/ft 2.50 / 3.35	FOUNDATION	TUBULAR STEEL O/(in) lb/ft 3.00	TUBULAR STEEL O/(in) lb/ft 3.50	TUBULAR STEEL O/(in) lb/ft 4.00	TUBULAR STEEL O/(in) lb/ft 5.00	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
WB	MM 0.010, LT	F	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 25 FT EAST OF WARM BROOK	X		
EB	MM 0.020, RT	A	R2-1	24	30		SPEED LIMIT 25			X				X												RETAIN EXISTING SIGN AND POST			
EB	MM 0.250, RT	A	W1-1MdR	36	36	FY		9.00								2		X								INSTALL NEW SIGN AND ON 2 POSTS 12 FT WEST OF POLE #V239/40		7	
		A	W13-1P	18	18	FY	15 MPH	2.25																		INSTALL NEW PLAQUE BELOW W1-1MdR SIGN ON LEFT HAND POST	X		
WB	MM 0.250, LT	E	W1-1MdR	36	36	FY		9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 12 FT WEST AND ACROSS FROM POLE #V239/40		7	
		E	W13-1P	18	18	FY	15 MPH	2.25																		INSTALL NEW PLAQUE BELOW W1-1MdR SIGN ON RIGHT HAND POST	X		
EB	MM 0.250, RT	A	W1-1R	30	30								X		X											REMOVE EXISTING SIGN AND POST ADJACENT TO POLE #V239/40			
WB	MM 0.291, LT	E F	W1-8L W1-8R	18 18	24 24	FY	B-B	3.00 3.00								1		X								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 15 FT WEST OF POLE #22/41/40	X		
WB	MM 0.305, LT	E F	W1-8L W1-8R	18 18	24 24	FY	B-B	3.00 3.00								1		X								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 95 FT WEST OF POLE #22/41/40	X		
WB	MM 0.320, LT	E F	W1-8L W1-8R	18 18	24 24	FY	B-B	3.00 3.00								1		X								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 175 FT WEST OF POLE #22/41/40	X		
WB	MM 0.330, LT	F	W1-6L	48	24	FY		8.00					X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS ADJACENT TO POLE #22/42/20T/4-3/51	X		
		F	OM4-1	18	18								X X X X		X X X X											REMOVE (4) EXISTING RED OBJECT MARKERS AND POSTS			
WB	MM 0.331, LT	E	W1-6R	48	24	FY		8.00								2		X								INSTALL NEW SIGN ON POSTS 15 FT WEST OF MAIL BOX	X		
							SHEET SUBTOTALS	SF 62.75	SF	EA 8				EA 8		EA 12		FT 180		EA	LB								
										EA 1	EA	EA	EA 7	EA 1	EA 7		FT	FT 150	FT		LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: dl0k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
ARLINGTON TRAFFIC SIGN SUMMARY 1

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 9 OF 49