STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - MIDDLEBURY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 1.490, RT	A	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 158 FT WEST AND ACROSS FROM POLE #4	X		
		A	W13-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W2-1 SIGN ON LEFT HAND POST	X		
WB	MM 1.490, LT	E	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 158 FT WEST OF POLE #4	X		
		E	W13-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W2-1 SIGN ON RIGHT HAND POST	X		
WB	MM 1.530, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 53 FT EAST OF POLE #4	X		
EB	MM 1.550, RT	A	TOWN SIGN	30	30		HIDDEN DRIVE AHEAD						I X		X											REMOVE EXISTING SIGN AND POST 158 FT EAST AND ACROSS FROM POLE #4			
EB	MM 1.600, RT	C	W14-1	30	30		DEAD END	6.25					I X		X	1		X								REPLACE EXISTING SIGN AND POST 158 FT SOUTH FROM POLE #151/2/27/38	X		
EB	MM 1.600, RT	C	TOWN SIGN	18	24		SLOW KIDS						~~X~~		X					SIGN REMOVED BY OTHER						REMOVE EXISTING SIGN AND POST 158 FT SOUTH FROM POLE #151/2/27/38			
EB	MM 1.610, RT	D	R1-1	30	30		STOP	6.25					I X		X	1		X								REPLACE EXISTING SIGN AND POST 106 FT SOUTH FROM POLE #151/2/27/38	X		
WB	MM 1.620, LT	H	R1-1	30	30		STOP	6.25					I X		X	1		X								REPLACE EXISTING SIGN AND POST 53 FT SOUTH AND ACROSS FROM POLE #151/2/27/38	X		
WB	MM 1.630, LT	G	R2-1	24	30		SPEED LIMIT 35	5.00					I X		X	1		X								REPLACE EXISTING SIGN AND POST ACROSS FROM POLE #151/2/27/38	X		
EB	MM 1.660, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					I X		X	1		X								REPLACE EXISTING SIGN AND POST 11FT SOUTH FROM POLE #2A	X		
WB	MM 1.700, LT	F	TOWN SIGN	36	36		DANGEROUS INTERSECTION AHEAD						I X		X											REMOVE EXISTING SIGN AND POST 200 FT NORTH AND ACROSS FROM POLE #2A			
WB	MM 1.700, LT	F	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 200 FT NORTH AND ACROSS FROM POLE #2A	X		
		F	W13-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW SIGN PLAQUE BELOW INTERSECTION WARNING SIGN ON LEFT HAND POST	X		
EB	MM 1.770, RT	A	W1-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 85 FT SOUTH FROM POLE #14/83-/54B	X		
										EA	EA	EA	EA ~~8~~ 7	EA	EA 8		FT	FT 195	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 73.75	SF	EA 8				EA 8		EA 13	FT 195			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
MIDDLEBURY TRAFFIC SIGN SUMMARY 2

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 16 OF 49