STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - MIDDLEBURY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 1.800, LT	F	W1-8L	18	24		B-B	3.00								1		X								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET ADJACENT TO POLE #15/93-1			
		E	W1-8R	18	24			3.00																					
WB	MM 1.825, LT	F	W1-8L	18	24		B-B	3.00								1		X								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON SIGN BRACKET 26 FT NORTH OF AND ACROSS FROM POLE #67/41/49			
		E	W1-8R	18	24			3.00																					
WB	MM 1.850, RT	F	W1-8L	18	24		B-B	3.00								1		X								INSTALL NEW BACK-TO-BACK CHEVRON SIGNS ON BRACKET ADJACENT TO POLE #15/92/185/55	X		
		E	W1-8R	18	24			3.00																					
WB	MM 2.000, LT	F	VW-276 H	30	30		DRIFTING SNOW	6.25								1		X								INSTALL NEW SIGN AND POST IN CLOSED POSTION 158 FT NORTH FROM POLE #89/58		7	
EB	MM 2.030, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS ACROSS FROM POLE #89/58	X		
WB	MM 2.150, LT	F	R2-1	30	36		SPEED LIMIT 40	7.50					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 634 FT NORTH FROM POLE #89/58	X		
EB	MM 2.190, RT	A	R1-1	30	30		STOP			X				X												RETAIN EXISTING STOP SIGN 845 FT NORTH AND ACROSS FROM POLE #89/58			
WB	MM 2.190, LT	H	R1-1	30	30		STOP			X				X												RETAIN EXISTING STOP SIGN 845 FT NORTH FROM POLE #89/58			
							SEMINARY STREET EXTENSION																					
SB	MM 0.000, LT	F	W1-10L	36	36			9.00					1			2		X								INSTALL NEW SIGN ON 2 POSTS ACROSS FROM POLE #40/27/10	X		
NB	MM 0.040, RT	A	R1-1	24	30		SPEED LIMIT 35	5.00					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 211FT EAST FROM POLE #40/27/10	X		
							FOOTE STREET																					
NB	MM 0.020, RT	A	R1-1	30	30		STOP	6.25				1	1 X		X	1		X								REPLACE EXISTING SIGN AND POST 370 FT WEST AND ACROSS FROM POLE #41-2	X		
NB	MM 0.030, RT	D	R1-1	30	30		STOP	6.25			1		2 X		X	1		X								REPLACE EXISTING SIGN AND POST 320 FT WEST AND ACROSS FROM POLE #41-2	X		
SB	MM 0.060, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00			1	1	2 X		X	1		X								REPLACE EXISTING SIGN AND POST 158 FT WEST FROM POLE #41-2	X		
NB	MM 0.110, RT	A	W3-1	24	30			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 106 FT NORTH AND ACROSS FROM POLE #41-2	X		
										EA 2	EA	EA	EA ~~5~~ 7	EA 2	EA 5		FT	FT 225	FT		LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 81.25	SF	EA 7				EA 7		EA 15	FT 225			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
MIDDLEBURY TRAFFIC SIGN SUMMARY 3

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 17 OF 49