STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - MIDDLETOWN SPRINGS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.085, RT	A	W13-1P	18	18		35 M.P.H.						X		X											REMOVE EXISTING SIGN AND POST 185 FT SOUTH OF DAYTON HILL RD			
EB	MM 0.085, RT	A	W1-4L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 185 FT SOUTH OF DAYTON HILL RD	X		
		A	W13-1P	18	18		35 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-4L SIGN ON THE SAME POST	X		
EB	MM 0.120, RT	D	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW STOP SIGN AND POST 143 FT SOUTH FROM POLE #7002/3/CTCVT/3	X		
EB	MM 0.150, RT	A	W1-6L	48	24			8.00					X		X X	2		X								REPLACE EXISTING SIGN AND POSTS NORTH OF POLE #7002/3/CTCVT/3	X		
EB	MM 0.150, RT	B	W1-6R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 16 FT NORTH OF POLE #7002/3/CTCVT/3 AND NORTH OF PREVIOUSLY INSTALLED W1-6L	X		
EB	MM 0.206, RT	A	OM-3R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 311FT NORTH OF POLE #7002/3/CTCVT/3 AT SOUTHEAST CORNER OF BRIDGE ABUTMENT	X		
WB	MM 0.206, LT	E	OM-3L	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 311FT NORTH OF AND ACROSS FROM POLE #7002/3/CTCVT/3 AT SOUTHWEST CORNER OF BRIDGE ABUTMENT	X		
EB	MM 0.217, RT	B	OM-3L	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 370 FT NORTH OF POLE #7002/3/CTCVT/3 AT NORTHEAST CORNER OF BRIDGE ABUTMENT	X		
WB	MM 0.217, LT	F	OM-3R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 370 FT NORTH OF AND ACROSS FROM POLE #7002/3/CTCVT/3 AT NORTHWEST CORNER OF BRIDGE ABUTMENT	X		
WB	MM 0.217, LT	F	W13-1P	18	18		35 M.P.H.						X		X											REMOVE SIGN AND POST 370 FT NORTH OF AND ACROSS FROM POLE #7002/3/CTCVT/3			
WB	MM 0.230, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REPLACE EXISTING SIGN AND POST 90 FT SOUTH OF POLE #7/187/83/1	X		
WB	MM 0.250, LT	F	W1-4L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 16 FT NORTH OF POLE #7/187/83/1	X		
		F	W13-1P	18	18		35 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-4L SIGN ON THE SAME POST	X		
EB	MM 0.295, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								REPLACE EXISTING SIGN AND POST 116 FT SOUTH OF AND ACROSS FROM POLE #189/99	X		
EB	MM 0.470, RT	A	W1-2R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 90 FT SOUTH OF POLE #196/VTEL/92	X		
													EA 5		EA 6			FT 210							LB			
							SHEET SUBTOTALS	SF 68.75	SF				EA 5		EA 6	EA 14		FT 210		EA				LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: dl0k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
MIDDLETOWN SPR. TRAFFIC SIGN SUMMARY 1

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 19 OF 49