

TRAFFIC SIGN SUMMARY SHEET 3 - MIDDLETOWN SPRINGS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS <small>SHS = STANDARD HIGHWAY SIGN BOOK</small>	SIGN DETAIL					
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE		RETAIN	REMOVE	1.75	2.00	2.50	FOUNDATION	3.00			3.50	4.00	5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																	lb/ft				lb/ft								
EB	MM 1.710, RT	C	VR-017	24	30			5.00				X		X	I		X						REPLACE EXISTING SIGN AND POST 85 FT SOUTH OF POLE #7/234/VTEL/56 AND SOUTH OF ORCHARD RD			5			
EB	MM 1.720, RT	D	RI-1	30	30			6.25				X		X	I		X						REPLACE EXISTING SIGN AND POST 32 FT SOUTH OF POLE #7/234/VTEL/56 AND NORTH OF ORCHARD RD	X					
EB	MM 1.750, RT	A	R2-1	24	30			5.00				X		X	I		X						REPLACE EXISTING SIGN AND POST 127 FT NORTH OF POLE #7/234/VTEL/56	X					
WB	MM 2.146, LT	F	R2-1	24	30			5.00				X		X	I		X						REPLACE EXISTING SIGN AND POST 1097 FT SOUTH OF AND ACROSS FROM POLE #CTC/34	X					
EB	MM 2.185, RT	C	VR-017	24	30			5.00				X		X	I		X						REPLACE EXISTING SIGN AND POST 891 FT SOUTH OF POLE #CTC/34			5			
WB	MM 2.190, LT	G	RI-1	30	30							X		X									REMOVE EXISTING SIGN AND POST 865 FT SOUTH OF AND ACROSS FROM POLE #CTC/34						
WB	MM 2.190, RT	G	WI-7	48	24			8.00							2		X						INSTALL NEW SIGN ON 2 POSTS 865 FT SOUTH OF AND ACROSS FROM POLE #CTC/34 DIRECTLY ACROSS FROM COY HILL ROAD	X					
EB	MM 2.195, RT	D	RI-1	30	30			6.25							I		X						INSTALL SIGN AND POST 818 FT SOUTH OF POLE #CTC/34	X					
EB	MM 2.250, RT	A	R2-1	24	30			5.00				X		X	I		X						REPLACE EXISTING SIGN AND POST 528 FT SOUTH OF POLE #CTC/34	X					
EB	MM 2.350, RT	A	WII-4	30	30			6.25							I		X						INSTALL SIGN AND POST 20 FT SOUTH OF POLE #CTC/34	X					
WB	MM 2.530, LT	F	WII-4	30	30			6.25							I		X						INSTALL SIGN AND POST ADJACENT TO POLE #262/28	X					
WB	MM 2.570, LT	F	WII-5	30	30							2	X		X								REMOVE EXISTING SIGN AND POST 211 FT NORTH OF POLE #262/08						
		F	TOWN SIGN	18	24							X											REMOVE EXISTING SIGN BELOW FARM CROSSING SIGN						
EB	MM 2.600, RT	A	R2-5A	24	30							X		X									REMOVE EXISTING SIGN AND POST 370 FT NORTH OF AND ACROSS FROM POLE #262/28						
EB	MM 2.600, RT	A	W3-5	36	36			9.00							2		X						INSTALL NEW SIGN ON 2 POSTS 370 FT NORTH OF AND ACROSS FROM POLE #262/28	X					
WB	MM 2.690, LT	F	R2-1	24	30			5.00				X		X	I		X						REPLACE EXISTING SIGN AND POST 106 FT SOUTH OF AND ACROSS FROM POLE #225	X					
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".											EA	EA	EA	EA	EA	EA	EA	FT	FT	FT		LB	LB	LB	LB	PROJECT NAME: STATEWIDE SOUTHWEST REGION PROJECT NUMBER: STP HRRR(II) FILE NAME: d:\0k322wrk.dgn PROJECT LEADER: JLS DESIGNED BY: NLA MIDDLETOWN SPR. TRAFFIC SIGN SUMMARY 3 SHEET 21 OF 49			
SHEET SUBTOTALS								SF 72.00	SF	EA II	EA 10	EA 14	FT 210	EA	LB														