STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 - MIDDLETOWN SPRINGS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 3.150, RT	A	M3-1	24	12		NORTH	2.00								2		X							2C	INSTALL NEW SIGN ASSEMBLY ON 2 POSTS 3854 FT SOUTH OF VT-133 AND WEST ROAD INTERSECTION AT THE SAME LOCATION (COLORS TO BE WHITE BACKGROUND WITH GREEN TEXT)	X		
		A	M1-5	30	24		VERMONT 133	5.00																		INSTALL NEW SIGN BELOW M3-1 SIGN ON LEFT HAND SIDE OF SIGN ASSEMBLY			E-136B
		A	M6-3	21	15		↑	2.19																		INSTALL NEW SIGN BELOW M1-5 SIGN ON LEFT HAND SIDE OF SIGN ASSEMBLY (COLORS TO BE WHITE BACKGROUND WITH GREEN SYMBOL)	X		
		A	M3-2	24	12		EAST	2.00																		INSTALL NEW SIGN BELOW M6-3 SIGN ON LEFT HAND SIDE OF SIGN ASSEMBLY (COLORS TO BE WHITE BACKGROUND WITH BLACK TEXT)	X		
		A	M1-6	30	24		140	5.00																		INSTALL NEW SIGN BELOW M3-2 SIGN ON LEFT HAND SIDE OF SIGN ASSEMBLY (COLORS TO BE BLACK ON WHITE BACKGROUND	X		
		A	M6-3	21	15		↑	2.19																		INSTALL NEW SIGN BELOW M1-6 SIGN ON LEFT HAND SIDE OF SIGN ASSEMBLY (COLORS TO BE WHITE BACKGROUND WITH BLACK SYMBOL)	X		
		A	M3-6	24	12		SOUTH	2.00																		INSTALL NEW SIGN ON RIGHT HAND SIDE OF SIGN ASSEMBLY BEGINNING AT THE TOP (COLORS TO BE WHITE BACKGROUND WITH GREEN TEXT)	X		
		A	M1-5	30	24		VERMONT 133	5.00																		INSTALL NEW SIGN BELOW M3-6 SIGN ON RIGHT HAND SIDE OF SIGN ASSEMBLY			E-136B
		A	M5-1R	21	15		↱	2.19																		INSTALL NEW SIGN BELOW M1-5 SIGN ON RIGHT HAND SIDE OF SIGN ASSEMBLY (COLORS TO BE WHITE BACKGROUND WITH GREEN SYMBOL	X		
EB	MM 3.185, RT	A	D1-1A	72	12		↑ West Rutland 11	6.00					1 X		X	2		X								REPLACE EXISTING SIGN ON 2 POSTS 185 FT NORTH OF PREVIOUSLY INSTALLED ROUTE MARKER ASSEMBLY		7	
		A	D1-1A	72	12		↑ Wallingford 11	6.00					1 X		X											REPLACE EXISTING SIGN BELOW WEST RUTLAND DESTINATION SIGN		7	
		A	D1-1A	72	12		Pawlet 11 →	6.00					1 X		X											REPLACE EXISTING SIGN BELOW WALLINGFORD DESTINATION SIGN		7	
EB	MM 3.210, RT	A	R1-1	30	30		STOP			X				X												RETAIN EXISTING SIGN AND POST 3432 FT SOUTH OF VT 133 ROUTE			
		A	R1-3	18	6		4-WAY						~~X~~													REMOVE EXISTING SIGN BELOW STOP SIGN 3432 FT SOUTH OF VT 133 ROUTE			
		A	R1-3P	18	6		ALL WAY	0.75	← REFER TO SHEET 24 OR 49 FOR NOTE #1																	INSTALL NEW SIGN BELOW STOP SIGN 3432 FT SOUTH OF VT 133 ROUTE	X		
										EA 1	EA	EA	EA ~~4~~ 3	EA 1	EA 3		FT	FT 60	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 46.32	SF	EA 5				EA 4		EA 4	FT 60			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: dl0k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
MIDDLETOWN SPR. TRAFFIC SIGN SUMMARY 5

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 23 OF 49