

TRAFFIC SIGN SUMMARY SHEET 2 - POULTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS <small>SHS = STANDARD HIGHWAY SIGN BOOK</small>	SIGN DETAIL						
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDA-TION	lb/ft			lb/ft					DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER				
																		1.75	2.00	2.50	3.00	3.50	4.00						5.00			
NB	MM 0.048, RT	A	SI-1	36	36	FYG		9.00							2		X							INSTALL NEW SIGN ON 2 POSTS 53 FT NORTH OF AND ACROSS FROM POLE #107/21	X							
		A	S4-3P	24	8	FYG		1.33																INSTALL NEW PLAQUE BELOW SI-1 ON THE SAME POSTS	X							
NB	MM 0.069, RT	A	S2-1	36	36								X	X										REMOVE EXISTING SIGN AND POST 174 FT NORTH OF AND ACROSS FROM POLE #107/21								
NB	MM 0.077, RT	A	M3-2	24	12			2.00							1		X							INSTALL NEW SIGN AND POST 121 FT SOUTH OF AND ACROSS FROM POLE #24 1/2, COLORS TO BE BLACK ON WHITE BACKGROUND	X							
		A	M1-6	30	24			5.00																INSTALL NEW SIGN BELOW CARDINAL DIRECTIONAL SIGN (EAST) ON SAME POST	X							
NB	MM 0.100, RT	A	SI-1	36	36	FYG		9.00							2		X							INSTALL NEW SIGN ON 2 POSTS ACROSS FROM POLE #24 1/2	X							
		A	W16-9P	24	12	FYG		2.00																INSTALL NEW PLAQUE BELOW SI-1 SIGN ON THE SAME POSTS	X							
NB	MM 0.127, RT	A	R8-3A	24	30								X	X										REMOVE EXISTING SIGN AND POST 280 FT SOUTH OF POLE #26/NET/986								
		A	TOWN SIGN	24	30								X											REMOVE EXISTING SIGN 280 FT SOUTH OF POLE #26/NET/986								
		A	R7-201	12	6								X											REMOVE EXISTING SIGN 280 FT SOUTH OF POLE #26/NET/986								
NB	MM 0.127, RT	A	R8-3	24	24			4.00								+	X							INSTALL NEW SIGN AND POST 280 FT SOUTH OF POLE #26/NET/986	X							
		A	M4-14	24	12			2.00																INSTALL NEW PLAQUE BELOW R8-3 ON THE SAME POST, COLORS TO BE BLACK ON WHITE BACKGROUND	X							
NB	MM 0.170, RT	A	R8-3	24	24			4.00							1		X							INSTALL NEW SIGN AND POST 53 FT SOUTH OF POLE #26/NET/986	X							
		A	M4-6	24	12			2.00																INSTALL NEW PLAQUE BELOW R8-3 ON THE SAME POST, COLORS TO BE BLACK ON WHITE BACKGROUND	X							
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".																																
SHEET SUBTOTALS								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
								41.33		4	2	4	2	7																		

PROJECT NAME: STATEWIDE SOUTHWEST REGION
 PROJECT NUMBER: STP HRRR(II)
 FILE NAME: d10k322wrk.dgn
 PROJECT LEADER: JLS
 DESIGNED BY: NLA
 POULTNEY TRAFFIC SIGN SUMMARY 2
 PLOT DATE: 15-JUL-2011
 DRAWN BY: ITS
 CHECKED BY: JLS
 SHEET 27 OF 49