
















TRAFFIC SIGN SUMMARY SHEET 3 - POULTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST	NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS <small>SHS = STANDARD HIGHWAY SIGN BOOK</small>	SIGN DETAIL					
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE			RETAIN	REMOVE	1.75	2.00	2.50	FOUNDATION	3.00			3.50	4.00	5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																		lb/ft				lb/ft								
SB	MM 0.180, LT	F	VW-054	30	30			6.25						I		X							INSTALL NEW SIGN AND POST 169 FT SOUTH OF AND ACROSS FROM POLE #29/29			7				
SB	MM 0.200, LT	F	SI-I	36	36									X	X								REMOVE EXISTING SIGN AND POST 169 FT SOUTH OF AND ACROSS FROM POLE #29/29							
		F	S4-3P	24	8									X									REMOVE EXISTING PLAQUE 169 FT SOUTH OF AND ACROSS FROM POLE #29/29							
		F	W2-2	30	30									X									REMOVE EXISTING SIGN 169 FT SOUTH OF AND ACROSS FROM POLE #29/29							
NB	MM 0.232, RT	A	R2-1	24	30			5.00							I	X							INSTALL NEW SIGN AND POST ADJACENT TO POLE #29/29	X						
SB	MM 0.232, LT	F	R2-1	24	30			5.00						X	X	I	X						REPLACE EXISTING SIGN AND POST ACROSS FROM POLE #29/29	X						
NB	MM 0.280, RT	A	SI-I	36	36	FYG		9.00							2	X							INSTALL NEW SIGN ON 2 POSTS 53 FT SOUTH OF FURNACE ST	X						
		A	WI6-7P	24	12	FYG	 ← SEE NOTE	2.00															INSTALL NEW SIGN BELOW SI-10N LEFT HAND POST	X						
SB	MM 0.282, LT	F	SI-I	36	36	FYG		9.00							2	X							INSTALL NEW SIGN AND ON 2 POSTS 42 FT SOUTH OF AND ACROSS FROM FURNACE ST	X						
		F	WI6-7P	24	12	FYG	 ← SEE NOTE	2.00															INSTALL NEW SIGN BELOW SI-10N LEFT HAND POST	X						
NB	MM 0.290, RT	D	RI-I	30	30			6.25							1	X							INSTALL NEW SIGN AND POST AT THE NORTHEAST CORNER OF FURNACE ST AND EAST MAIN ST INTERSECTION	X						
SB	MM 0.330, LT	F	SI-I	36	36	FYG		9.00							2	X							INSTALL NEW SIGN ON 2 POSTS ACROSS FROM POLE #33	X						
		F	WI6-7P	24	8	FYG		1.33															INSTALL NEW PLAQUE BELOW SI-10N THE SAME POSTS	X						
NB	MM 0.404, RT	A	R2-1	24	30			5.00							I	X							INSTALL NEW SIGN AND POST 380 FT SOUTH OF POLE #39/39	X						
SB	MM 0.404, LT	F	R2-1	24	30			5.00						2	X	X	I	X					REPLACE EXISTING SIGN AND POST 380 FT SOUTH OF AND ACROSS FROM POLE #39/39	X						
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".																														
SHEET SUBTOTALS								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
								64.84		5	3	12																		

PROJECT NAME: STATEWIDE SOUTHWEST REGION
 PROJECT NUMBER: STP HRRR(II)
 FILE NAME: d10k322wrk.dgn
 PROJECT LEADER: JLS
 DESIGNED BY: NLA
 POULTNEY TRAFFIC SIGN SUMMARY 3

PLOT DATE: 15-JUL-2011
 DRAWN BY: ITS
 CHECKED BY: JLS
 SHEET 28 OF 49