STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 - POULTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 1.472, RT	D	R1-1	30	30		STOP	6.25				1				1		X								INSTALL NEW SIGN AND POST 64 FT SOUTH OF POLE #76/76	X		
NB	MM 1.476, RT	D	R1-1	30	30		STOP						2 X		X											REMOVE EXISTING SIGN AND POST 42 FT SOUTH OF POLE #76/76			
NB	MM 1.476, RT	D	OM1-1	18	18			2.25								1		X								INSTALL NEW SIGN AND POST 42 FT SOUTH OF POLE #76/76 AT POINT OF ISLAND AT CORRECT HEIGHT	X		
NB	MM 1.479, RT	D	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST 26 FT SOUTH OF POLE #76/76	X		
NB	MM 1.480, RT	A	W11-2	30	30	FYG		6.25								1		X								INSTALL NEW SIGN AND POST 21FT SOUTH OF POLE #76/76	X		
		A	W16-7P	24	12	FYG		2.00																		INSTALL NEW PLAQUE BELOW W11-2 ON THE SAME POST	X		
SB	MM 1.480, LT	F	W11-2	30	30	FYG		6.25								1		X								INSTALL NEW SIGN AND POST 21FT SOUTH OF AND ACROSS FROM POLE #76/76	X		
			W16-7P	24	12	FYG		2.00																		INSTALL NEW PLAQUE BELOW W11-2 ON THE SAME POST	X		
NB	MM 1.485, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					1 X		X											REMOVE EXISTING SIGN AND POST 6 FT NORTH OF POLE #76/76			
NB	MM 1.506, RT	A	R2-1	24	30		SPEED LIMIT 35									1		X								INSTALL NEW SIGN AND POST 116 FT NORTH OF POLE #76/76	X		
NB	MM 1.530, RT	C	R1-2	36	36		YIELD	3.89								2		X								INSTALL NEW SIGN ON 2 POSTS SOUTH OF "ON THE GREEN" ROAD WHERE THE MOST SOUTHERLY SLIPRAMP INTERSECTS "ON THE GREEN" ROAD	X		
NB	MM 1.536, RT	D	R1-1	30 ~~24~~	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST ON THE SOUTHWEST CORNER OF EAST MAIN ST AND "ON THE GREEN" ROAD INTERSECTION	X		
SB	MM 1.536, LT	F	W11-2	30	30								1 X		X											REMOVE EXISTNG SIGN AND POST 116 FT SOUTH OF POLE #79/79	X		
SB	MM 1.536, LT	F	W11-2	30 ~~24~~	30	FYG		6.25								1		X								INSTALL NEW SIGN AND POST 116 FT SOUTH OF POLE #79/79	X		
		A	W16-9P	24	12	FYG	AHEAD	2.00																		INSTALL NEW PLAQUE BELOW W11-2 SIGN ON THE SAME POST	X		
NB	MM 1.558, RT	D	R1-1	30	30		STOP	6.25				1	2 X		X	1		X								REPLACE EXISTING SIGN AND POST ACROSS FROM POLE #79/79 FOR THE MOST NORTHERLY SLIP RAMP OF "ON THE GREEN" ROAD	X		
										EA	EA	EA	EA ~~4~~ 6	EA	EA 4			FT 165	FT						LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 60.89	SF	EA 4				EA 4		EA 11		FT 165		EA					LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
POULTNEY TRAFFIC SIGN SUMMARY 5

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 30 OF 49