STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7 - POULTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 1.770, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 845 FT NORTH OF AND ACROSS FROM POLE #7/80/186/80	X		
		A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-2L ON THE SAME POST	X		
NB	MM 1.820, RT	A	W1-6L	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 1214 FT SOUTH OF AND ACROSS FROM POLE #7/93	X		
NB	MM 1.820, RT	B	W1-6R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 1214 FT SOUTH OF AND ACROSS FROM POLE #7/93	X		
SB	MM 1.880, LT	F	W1-2R	30	30			6.25					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 898 FT SOUTH OF POLE #7/93	X		
		F	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-2R ON THE SAME POST	X		
NB	MM 2.030, RT	A	W1-2R	30	30								1 X		X											REMOVE EXISTING SIGN AND POST 106 FT SOUTH OF AND ACROSS FROM POLE #7/93			
SB	MM 2.100, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 53 FT SOUTH OF POLE #95/96	X		
NB	MM 2.135, RT	A	W1-3R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #7/96	X		
		A	W13-1P	18	18		25 K.P.H.	2.25																		INSTALL NEW PLAQUE BELOW W1-3R ON THE SAME POST	X		
NB	MM 2.175, RT	A	OM-3R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE #98 AT THE SOUTHEAST CORNER OF BRIDGE ABUTMENT	X		
SB	MM 2.175, LT	E	W1-8R	18	24								2 X		X											REMOVE EXISTING SIGN AND POST ADJACENT TO POLE #98			
		E	OM1-1	18	18																					REMOVE EXISTING SIGN ADJACENT TO POLE #98			
SB	MM 2.175, LT	E	OM-3L	12	36			3.00								1		X								INSTALL NEW SIGN AND POST ADJACENT TO POLE #98 AT SOUTHWEST CORNER OF BRIDGE ABUTMENT	X		
NB	MM 2.190, RT	B	OM-3R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 79 FT NORTH OF AND ACROSS FROM POLE #98 AT NORTHEAST CORNER OF BRIDGE ABUTMENT	X		
SB	MM 2.190, LT	F	OM-3R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 79 FT NORTH OF POLE #98 AT NORTHWEST CORNER OF BRIDGE ABUTMENT	X		
										EA	EA	EA	EA ~~4~~ 5	EA	EA 4		FT	FT 180	FT		LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 58.50	SF	EA 4				EA 4		EA 12	FT 180			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
POULTNEY TRAFFIC SIGN SUMMARY 7

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 32 OF 49