STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8 - POULTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 2.190, LT	H	RI-1	30	30		STOP	6.25			1		2			1		X								INSTALL NEW SIGN AND POST AT THE SOUTHWEST CORNER OF FINEL HOLLOW RD AND EAST MAIN ST INTERSECTION	X		
SB	MM 2.200, LT	G	R2-1	24	30		SPEED LIMIT 35	5.00					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 53 FT SOUTH OF POLE #>/98/NET/186•99	X		
SB	MM 2.210, LT	F	WI-6L	48	24		←	8.00					1 X		X	2		X								REPLACE EXISTING SIGN AND INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE #>/98/NET/186/99	X		
		F	OMI-1	18	18		◆						1 X													REMOVE EXISTING SIGN ADJACENT TO POLE #>/98/NET/186/99			
SB	MM 2.210, LT	E	WI-6R	48	24		→	8.00					1 X		X	2		X								REPLACE EXISTING SIGN AND INSTALL NEW SIGN ON 2 POSTS ADJACENT TO POLE #>/98/NET/186/99	X		
		E	OMI-1	18	18		◆						1 X													REMOVE EXISTING SIGN ADJACENT TO POLE #>/98/NET/186/99			
NB	MM 2.285, RT	A	WI-6L	48	24		←	8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 111FT SOUTH OF POLE #9/101/102	X		
NB	MM 2.285, RT	A	R2-1	24	30		SPEED LIMIT 40						2 X		X											REMOVE EXISTING SIGN AND POST 111FT SOUTH OF POLE #9/101/102			
NB	MM 2.285, RT	B	WI-6R	48	24		→	8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 111FT SOUTH OF POLE #9/101/102	X		
SB	MM 2.340, LT	F	WI-3R	30	30		↱	6.25								1		X								INSTALL NEW SIGN AND POST ADJACENT TO POLE#7/102	X		
		F	WI3-1P	18	18		25 MPH	2.25																		INSTALL NEW PLAQUE BELOW WI-3R ON THE SAME POST	X		
NB	MM 2.420, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST ACROSS TO POLE #106/106	X		
SB	MM 2.420, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST ADJACENT TO POLE #106/	X		
SB	MM 2.800, RT	F	VW-054	30	30		HIDDEN DRIVE RIGHT NOTE #4	6.25					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 686 FT SOUTH OF AND ACROSS FROM POLE #7/123		7	
SB	MM 2.930, LT	F	TOWN SIGN	30	30		HIDDEN DRIVE						1 X		X											REMOVE EXISTING SIGN AND POST ADJACENT TO POLE #7/123			
SB	MM 3.100, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 898 FT NORTH OF AND ACROSS FROM POLE #7/123	X		
										EA	EA	EA	EA ~~9~~ 12	EA	EA 7			FT 225				LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 73.00	SF	EA 9				EA 7		EA 15		FT 225		EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

NOTE #4: REFERENCE SHEET 34 OR 49

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
POULTNEY TRAFFIC SIGN SUMMARY 8

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 33 OF 49