STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 9 - POULTNEY

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) 1.75 lb/ft 1.88 | SQUARE STEEL (in) 2.00 lb/ft 2.42 | SQUARE STEEL (in) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(in) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(in) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(in) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHS = STANDARD HIGHWAY SIGN BOOK | SIGN DETAIL DETAIL IN SHS | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SB | MM 3.108, LT | H | RI-1 | 30 | 30 | | STOP | 6.25 | | | | 1 | 2 X | | X | 1 | | X | | | | | | | | REPLACE EXISTING SIGN AND POST AT THE SOUTHWEST CORNER OF HAMPSHIRE HOLLOW RD AND EAST MAIN ST INTERSECTION | X | | |
| NB | MM 3.110, RT | C | WI-7 | 48 | 24 | | | 8.00 | | | | | | | X | 2 | | X | | | | | | | | INSTALL NEW SIGN ON 2 POSTS LOCATED ADJACENT TO POLE #410/128 DIRECTLY ACROSS FROM HAMPSHIRE HOLLOW ROAD | X | | |
| NB | MM 3.140, RT | A | R2-1 | 24 | 30 | | SPEED LIMIT 40 | 5.00 | | | | | | | X | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST ADJACENT TO POLE #7/129/129/NET | X | | |
| NB | MM 3.170, RT | A | R2-1 | 24 | 30 | | SPEED LIMIT 40 | | | | | | 1 X | | X | | | | | | | | | | | REMOVE EXISTING SIGN AND POST 158 FT NORTH OF POLE #7/129/129/NET | | | |
| NB | MM 3.500, RT | A | WI-2L | 30 | 30 | | | 6.25 | | | | | | | X | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST ADJACENT TO POLE #138/NET | X | | |
| NB | MM 3.539, RT | A | WII-6 | 30 | 30 | | SNOW MOBILE | | | | | | 1 X | | X | | | | | | | | | | | REMOVE EXISTNG SIGN AND POST 322 FT SOUTH OF POLE #186/140/NET | | | |
| NB | MM 3.540, RT | A | WI-8L | 18 | 24 | | | | | | | | 1 X | | X | | | | | | | | | | | REMOVE EXISTING SIGN AND POST 317 FT SOUTH OF POLE #186/140/NET | | | |
| | | B | WI-8R | 18 | 24 | | | | | | | | 1 X | | | | | | | | | | | | | REMOVE EXISTING SIGN 317 FT SOUTH OF POLE #186/140/NET | | | |
| NB | MM 3.600, RT | A | WII-6H | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST IN THE CLOSED POSTION ADJACENT TO POLE #186/140/NET | X | | |
| SB | MM 3.730, LT | F | WII-6H | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST IN THE CLOSED POSTION ADJACENT TO POLE #7/148/146/NET | X | | |
| SB | MM 3.766, LT | F | WII-6 | 30 | 30 | | SNOW MOBILE | | | | | | 1 X | | X | | | | | | | | | | | REMOVE EXISTING SIGN AND POST 190 FT NORTH OF POLE #7/148/1445/NET | | | |
| SB | MM 3.766, LT | F | WI-4L | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 190 FT NORTH OF POLE #7/148/146/NET | X | | |
| SB | MM 3.780, LT | H | RI-1 | 30 | 30 | | STOP | 6.25 | | | | 2 | 2 X | | X | 1 | | X | | | | | | | | REPLACE EXISTING SIGN AND POST AT THE SOUTHWEST CORNER OF TOWN FARM ROAD AND EAST MAIN STREET INTERSECTION | X | | |
| | | G | VR-017 | 24 | 30 | | LEGAL LOAD LIMIT 24,000 POUNDS | | | | | | 2 X | | | | | | | | | | | | | REMOVE EXISTING SIGN AT THE SOUTHWEST CORNER OF TOWN FARM ROAD AND EAST MAIN STREET INTERSECTION | | | |
| SB | MM 2.800 | F | VW-054 | 30 | 30 | | HDR | | | | 1 | | 1 | | | | | | | | | | | | | NOTE #4: SIGN NEEDED TO BE RELOCATED, REFERENCE SHEET 33 OR 49 | | | |
| SB | MM 2.780 | F | VW-054 | 30 | 30 | | HDR | | | | | 1 | | | | | | | | | | | | | | NEED NEW ANCHOR | | | |
| | | | | | | | | | | EA | EA | EA 4 | EA 8 12 | EA | EA 7 | | FT | FT 135 | FT | | LB | LB | LB | LB | | | | | |
| | | | | | | | **SHEET SUBTOTALS** | SF 50.50 | SF | EA 8 | | | | EA 7 | | EA 9 | FT 135 | | | EA | LB | | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(II)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
POULTNEY TRAFFIC SIGN SUMMARY 9

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 34 OF 49