STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10 - POULTNEY

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 3.800, LT	G	R12-1	24	30		WEIGHT LIMIT 12 TONS	5.00								1		X								INSTALL NEW SIGN AND POST 20 FT SOUTHEAST OF POLE #150/18L/149/NET	X		
		G	W14-2	30	30		NO OUTLET	6.25								1		X								INSTALL NEW SIGN AND POST 6 FT APART FROM R12-1SIGN AND POST, AND 20 FT SOUTHEAST OF POLE #150/18L/149/NET	X		
SB	MM 4.000, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 222 FT SOUTH OF MORSE HOLLOW RD	X		
SB	MM 4.040, LT	H	R1-1	30	30		STOP	6.25					1 X		X	1		X								REPLACE EXISTING SIGN AND POST AT THE SOUTH WEST CORNER OF MORSE HOLLOW RD AND EAST MAIN ST INTERSECTION	X		
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						2 X													REMOVE EXISTING SIGN AND POST AT THE SOUTHWESTCORNER OF MORSE HOLLOW ROAD AND EAST MAIN STREET INTERSECTION			
SB	MM 4.042, LT	G	TOWN SIGN	24	30		SPEED ZONE AHEAD						1 X		X											REMOVE EXISTING SIGN AND POST AT THE NORTHWEST CORNER OF MORSE HOLLOW RD AND EAST MAIN ST INTERSECTION			
SB	MM 4.042, LT	G	R12-1	24	30		WEIGHT LIMIT 12 TONS	5.00					1 X		X	1		X								REPLACE EXISTING SIGN AND POST ADJACENT TO POLE #708/2	X		
		G	R2-1	24	30		SPEED LIMIT 35	5.00					1 X													REPLACE EXISTING SIGN AND INSTALL NEW SIGN BELOW R12-1SIGN ON THE SAME POST	X		
		G	TOWN SIGN	24	30		CAUTION TRUCK ENTRANCE						1 X													REMOVE EXISTING SIGN BELOW R12-1ON SAME POST			
NB	MM 4.055, RT	A	OM-3R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 69 FT NORTH OF MORSE HOLLOW RD AT THE SOUTHEAST CORNER OF THE BRIDGE ABUTMENT	X		
SB	MM 4.055, LT	E	OM-3L	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 69 FT NORTH OF AND ACROSS FROM MORSE HOLLOW RD AT THE SOUTHWEST CORNER OF THE BRIDGE ABUTMENT	X		
NB	MM 4.065, RT	B	OM-3L	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 121FT NORTH OF MORSE HOLLOW RD AT THE NORTHEAST CORNER OF THE BRIDGE ABUTMENT	X		
SB	MM 4.065, LT	F	OM-3R	12	36			3.00								1		X								INSTALL NEW SIGN AND POST 121FT NORTH OF MORSE HOLLOW ROAD AT THE NORTHWEST CORNER OF THE BRIDGE ABUTMENT	X		
NB	MM 4.070, RT	A	W1-2L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 370 FT SOUTH OF POLE #18-3/5	X		
		A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW THE W1-2L SIGN ON THE SAME POST	X		
							SHEET SUBTOTALS	SF 53.00	SF	EA 7				EA 4		EA 10		FT 150		EA		LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
POULTNEY TRAFFIC SIGN SUMMARY 10

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 35 OF 49