STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - POWNAL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.010, LT	F	R1-1	30	30		STOP			X				X												RETAIN EXISTING SIGN AND POST 53 FT NORTH OF ROUTE US-7			
NB	MM 0.029, RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					1 X		1 X	1		X								REPLACE EXISTING SIGN AND POST 153 FT NORTH OF ROUTE US-7 AND 110 FT SOUTH OF A UTILITY POLE WITH NO NUMBER		5	
		A	R2-1	24	30		SPEED LIMIT 35	5.00																		INSTALL NEW R2-1 SIGN BELOW VR-017 ON THE SAME POST	X		
NB	MM 0.045, RT	A	R2-1	24	30		SPEED LIMIT 35						1 X		1 X											REMOVE EXISTING SIGN AND POST 238 FT NORTH FROM ROUTE US-7			
SB	MM 0.070, LT	H	R1-1	30	30		STOP	6.25			1	1	2 X		2 X	1		X								REPLACE EXISTING SIGN AND POST AT THE SOUTHWEST CORNER OF MANN HILL RD AND NILES SCHOOL RD INTERSECTION	X		
SB	MM 0.071, LT	G	W14-1	30	30		DEAD END						1 X		1 X											REMOVE EXISTING SIGN AND POST ADJACENT TO POLE #4732/6/15-8/1			
SB	MM 0.071, LT	G	W14-2	30	30		NO OUTLET	6.25								1		X								INSTALL NEW SIGN AND POST ADJACENT TO POLE #4732/6/15-8/1	X		
NB	MM 0.076, RT	A	W1-5L	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 32 FT NORTH AND ACROSS FROM POLE #4732/6/15-8/1	X		
		A	W7-3aP	24	18		NEXT 2 MILES	3.00																		INSTALL NEW SIGN BELOW W1-5 ON LEFT HAND POST	X		
		A	W13-1	18	18		20 M.P.H.	2.25																		INSTALL NEW SIGN BELOW W1-5 ON RIGHT HAND POST	X		
NB	MM 0.120, RT	A	W1-6L	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 270 FT NORTH OF AND ACROSS FROM POLE #4732/6/15-8/1	X		
NB	MM 0.120, RT	B	W1-6R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2 POSTS 270 FT NORTH OF AND ACROSS FROM POLE #4732/6/15-8/1	X		
NB	MM 0.158, RT	A	VW-213	30	30		NARROW ROAD	6.25								1		X								INSTALL NEW SIGN AND POST 465 FT NORTH OF AND ACROSS FROM POLE #4732/6/15-8/1	X		
			W13-1P	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW VW-213 ON THE SAME POST	X		
							SHEET SUBTOTALS	SF 61.25	SF	EA 5				EA 5		EA 10		FT 150		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME:	STATEWIDE SOUTHWEST REGION
PROJECT NUMBER:	STP HRRR(11)
FILE NAME: d10k322wrk.dgn	PLOT DATE: 15-JUL-2011
PROJECT LEADER: JLS	DRAWN BY: ITS
DESIGNED BY: NLA	CHECKED BY: JLS
POWNAL TRAFFIC SIGN SUMMARY 1	SHEET 39 OF 49