STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - POWNAL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.421, RT	A	TOWN SIGN	18	24		SLOW CHILDREN						1 X		1 X											REMOVE EXISTING SIGN AND POST 153 FT SOUTH OF PRATT RD			
NB	MM 0.450, RT	C	W14-1	30	30		DEAD END						1 X		1 X											REMOVE EXISTING SIGN AND POST SOUTH OF PRATT RD			
NB	MM 0.450, RT	C	W14-2	30	30		NO OUTLET	6.25								1		X								INSTALL NEW SIGN AND POST SOUTH OF PRATT RD	X		
NB	MM 0.455, RT	D	R1-1	30	30		STOP	6.25				1	2 X		2 X	1		X								REPLACE EXISTING SIGN AND POST NORTHEAST OF PRATT RD AND NILES SCHOOL RD INTERSECTION	X		
SB	MM 0.558, LT	F	TOWN SIGN	18	24		SLOW CHILDREN						1 X		1 X											REMOVE EXISTING SIGN AND POST 116 FT SOUTH OF AND ACROSS FROM THE BEGINNING OF GUARDRAIL			
NB	MM 0.642, RT	A	W8-9	36	36		NO SHOULDER	9.00					1 X		1 X	2		X								REPLACE EXISTING SIGN AND INSTALL ON 2 POSTS 1014 FT NORTH OF PRATT RD	X		
NB	MM 1.115, RT	A		6	8		(1) TYPE II - 6"X8" WHITE DELINEATOR																			INSTALL NEW DELINEATOR 1257 FT NORTH OF LAVINO ROAD IN FRONT OF TREE THAT ENCROACHES INTO ROADWAY		6	
SB	MM 1.234, LT	F	VW-213	30	30		NARROW ROAD	6.25								1		X								INSTALL NEW SIGN AND POST 1077 FT SOUTH OF HIDDEN VALLEY RD		8	
		F	W13-1	18	18		25 M.P.H.	2.25																		INSTALL NEW PLAQUE BELOW VW-213 ON THE SAME POST	X		
SB	MM 1.429, LT	F	W1-5R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 79 FT SOUTH OF AND ACROSS FROM POLE #25/2	X		
		F	W7-3aP	24	18		NEXT 2 MILES	3.00																		INSTALL NEW PLAQUE BELOW W1-5 ON THE SAME POST	X		
NB	MM 1.432, RT	A B		6	8		(2) TYPE II - 6"X8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (2) ON SEPARATE POSTS, ONE FACING EACH DIRECTION OF TRAVEL ON EITHER SIDE OF TREE THAT ENCROACHES INTO THE ROAD		6	
SB	MM 1.433, LT	H	R1-1	30	30		STOP	6.25			1	1	2 X		2 X	1		X								REPLACE EXISTING SIGN AND POST 58 FT SOUTH OF AND ACROSS FROM POLE #25/2	X		
NB	MM 1.454, RT TO MM 1.522, RT	A B		6	8		(~~14~~ 7) TYPE II - 6"X8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (14) BACK-TO-BACK 60 FT APART ON 7 POSTS, INSTALL FIRST 53 FT NORTH OF POLE #25/2		6	
NB	MM 1.528, RT	D	R1-1	30	30		STOP	6.25			1	1	2 X		2 X	1		X								REPLACE EXISTING SIGN AND POST 127 FT NORTH OF POLE #25/4	X		
										EA	EA	EA 3	EA ~~7~~ 10	EA	EA 7		FT	FT 120	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 51.75	SF	EA 7				EA 7		EA 8	FT 120			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
POWNAL TRAFFIC SIGN SUMMARY 2

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 40 OF 49