

TRAFFIC SIGN SUMMARY SHEET 4

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL					
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	PLAIN		FLUORESCENT	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER	
																														lb/ft
NB	MM 2.458, RT	D	RI-1	30	30			6.25				1				X								REPLACE EXISTING SIGN AND POST NORTHEAST OF SWEET RD AND NILES SCHOOL RD INTERSECTION	X					
SB	MM 2.555, LT	F	WI-6L	48	24			8.00								2	X							INSTALL NEW SIGN ON 2 POSTS 496 FT SOUTH OF AND ACROSS FROM POLE #43/1	X					
SB	MM 2.555, LT	E	WI-6R	48	24			8.00								2	X							INSTALL NEW SIGN ON 2 POSTS 496 FT SOUTH OF AND ACROSS FROM POLE #43/1	X					
NB	MM 2.750, RT	A	WI-3	30	30			6.25								1	X							INSTALL NEW SIGN AND POST 200 FT SOUTH OF POLE #15T/3/16-1	X					
		A	WI3-1	18	18			2.25																INSTALL NEW PLAQUE BELOW WI-3L ON THE SAME POST	X					
NB	MM 2.782, RT	A	WI-6L	48	24			8.00								2	X							INSTALL NEW SIGN ON 2 POSTS 32 FT SOUTH OF POLE #15T/3/16-1	X					
		B	WI-6R	48	24			8.00								2	X							INSTALL NEW SIGN ON 2 POSTS 32 FT SOUTH OF POLE #15T/3/16-1	X					
SB	MM 2.892, LT	F	WI-3L	30	30			6.25								1	X							INSTALL NEW SIGN AND POST ADJACENT TO THE RED SHED	X					
		F	WI3-1	18	18			2.25																INSTALL NEW PLAQUE BELOW WI-3L ON THE SAME POST	X					
NB	MM 2.995, RT	A	WI-IL	30	30			6.25								1	X							INSTALL NEW SIGN AND POST 40 FT NORTH FROM DRIVE AND MAILBOX #837	X					
		A	WI3-1	18	18			2.25																INSTALL NEW PLAQUE BELOW WI-IL ON THE SAME POST	X					
SB	MM 3.065, LT	F	WI-IR	30	30			6.25								1	X							INSTALL NEW SIGN AND POST 143 FT SOUTH OF POLE #43/13	X					
		F	WI3-1	18	18			2.25																INSTALL NEW PLAQUE BELOW WI-IR ON THE SAME POST	X					
NB	MM 3.104, RT	A B					(2) TYPE II - 6"X8" WHITE DELINEATORS																	INSTALL NEW DELINEATORS (2) BACK-TO-BACK ON A SINGLE POST 63 FT NORTH AND ACROSS FROM POLE #43/13 IN FRONT OF TREE THAT ENCROACHES INTO ROADWAY		6				
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".										EA	EA	EA	EA	EA	EA		FT	FT	FT	LB	LB	LB	LB							
SHEET SUBTOTALS								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
								72.25		1	1	2	1	1	1	1	13	195	195	195	EA	EA	EA	EA	EA	EA	EA	EA	EA	

PROJECT NAME: STATEWIDE SOUTHWEST REGION
 PROJECT NUMBER: STP HRRR(II)
 FILE NAME: d:\0k322wrk.dgn
 PROJECT LEADER: JLS
 DESIGNED BY: NLA
 POWNAL TRAFFIC SIGN SUMMARY 4
 PLOT DATE: 15-JUL-2011
 DRAWN BY: ITS
 CHECKED BY: JLS
 SHEET 42 OF 49