STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 - POWNAL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 3.276, LT	F	TOWN SIGN	30	30		HIDDEN DRIVE						1 X		X											REMOVE EXISTING SIGN AND POST ADJACENT TO POLE #43/10/X			
SB	MM 3.276, LT	F	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1		X								INSTALL NEW SIGN AND POST ADJACENT TO POLE #43/10/X		7	
NB	MM 3.283, RT	A	W1-3R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 37 FT NORTH OF AND ACROSS FROM POLE #43/10/X	X		
		A	W13-1P	18	18		20 MPH	2.25																		INSTALL NEW PLAQUE BELOW W1-3R ON THE SAME POST	X		
NB	MM 3.288, RT	A		6	8		(1) TYPE II - 6"X8" WHITE DELINEATOR																			INSTALL NEW DELINEATOR 63 FT NORTH OF AND ACROSS FROM POLE #43/10/8 IN FRONT OF TREE THAT ENCROACHES INTO THE ROADWAY		6	
NB	MM 3.320, RT	A		6	8		(2) TYPE II - 6"X8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (2) ON SEPARATE POSTS, ONE FACING EACH DIRECTION OF TAVEL ON EITHER SIDE OF THE TREE THAT ENCROACHES INTO THE ROADWAY 227 FT SOUTH OF POLE #9		6	
SB	MM 3.395, LT	F	W1-3R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST ADJACENT TO POLE #43/9/88	X		
		F	W13-1P	18	18		20 MPH	2.25																		INSTALL NEW PLAQUE BELOW W1-3R ON THE SAME POST	X		
SB	MM 3.619, LT	F	R2-1	24	30		SPEED LIMIT 35						1 X		X											REMOVE EXISTING SIGN AND POST 502 FT SOUTH OF AND ACROSS FROM POLE #43/5/2			
		F	W11-4	24	24								1 X													REMOVE EXISTING SIGN 502 FT SOUTH OF AND ACROSS FROM POLE #43/5/2			
SB	MM 3.718, LT	F	W11-7	30	30			6.25					1 X		X	1		X								REPLACE EXISTING SIGN AND POST 26 FT NORTH OF AND ACROSS FROM POLE #43/5/2	X		
NB	MM 3.750, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2 POSTS 74 FT SOUTH OF POLE #43/4/12/1	X		
NB	MM 3.811, RT	A	R1-1	30	30		STOP	6.25					2 X		X	1		X								REPLACE EXISTING SIGN AND POST 248 FT NORTH OF POLE #43/4/12/1	X		
NB	MM 3.811, RT	J	D3-1	60	12		Barber Pond Rd	5.00					1 X		X	2		X								REPLACE EXISTING SIGN AND POST AND INSTALL NEW SIGN ON 2 POSTS DIRECTLY ACROSS FROM THE INTERSECTION OF NILES SCHOOL ROAD ON PARBER POND ROAD		8	
NB	MM 3.811, RT	C/D	D3-1	60	12		Niles School Rd	5.00								2		X								INSTALL NEW SIGN ON 2 POSTS 2 FEET EAST OF STOP SIGN		8	
SB	MM 3.811, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 248 FT NORTH OF AND ACROSS FROM POLE #43/4/12/1	X		
										EA	EA	EA	EA ~~6~~ 7	EA	EA 5			FT 180	FT			LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 59.75	SF	EA 6				EA 5		EA 12		FT 180		EA		LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: dl0k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
POWNAL TRAFFIC SIGN SUMMARY 5

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 43 OF 49