STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – TOWN TOTALS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							ARLINGTON TOTAL TSS SHEET 4	~~143.25~~ 148.75		2			~~12~~ 13	2	12	28		420											
							CASTLETON TOTAL TSS SHEET 6	30.83		1			~~2~~ 3	1	2	5		75											
							MIDDLEBURY TOTAL TSS SHEET 10	221.50		2			~~24~~ 26	2	24	39		585											
							MIDDLETOWN SPRINGS TOTAL TSS SHEET 17	283.51		4			~~46~~ 45	4	33	51		765											
							POULTNEY TOTAL TSS SHEET 30	~~623.69~~ 621.68					~~86~~ 111		59	112		1680											
							POWNAL TOTAL TSS SHEET 36	314.41		1			~~20~~ 27	1	19	56		840											
							PROJECT GRAND TOTALS	SF ~~1617.19~~ 1620.68	SF	EA 200				EA 159		EA 291		FT 4365		EA			LB						
										EA 10	EA	EA	EA ~~190~~ 225	EA 10	EA 149		FT	FT 4365	FT		LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(11)

FILE NAME: d10k322wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
TOWN TOTAL TRAFFIC SIGN SUMMARY 1

PLOT DATE: 15-JUL-2011
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 45 OF 49