

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
														BEGIN OPTION DD					
									1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB #1)	540.10	-			
									1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (APPROACH SLAB #1)	900.645	-			
														END OPTION DD					
														BEGIN OPTION EE					
									1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB #2)	540.10	-			
									1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (APPROACH SLAB #2)	900.645	-			
														END OPTION EE					
							250				250		LF	8 INCH UNDERDRAIN PIPE	605.11	1			
							2				2		EACH	UNDERDRAIN FLUSHING BASIN	605.95	-			
							35				35		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							90				90		CY	STONE FILL, TYPE II	613.11	5			
									278		278		CY	STONE FILL, TYPE IV	613.13	1			
							130				130		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	0.3			
							1				1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			
							175				175		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	6.5			
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
									4		4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72	-			
							75				75		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	2			
							80				80		LF	TEMPORARY TRAFFIC BARRIER	621.90	-			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			
							1400				1400		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	-			
							1400				1400		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	-			
							1400				1400		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	-			
							1400				1400		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	-			
							90				90		EACH	LINE STRIPING TARGETS	646.76	-			
							180		312		492		SY	GEOTEXTILE UNDER STONE FILL	649.31	1.7			
								300			300		SY	GEOTEXTILE FOR SILT FENCE	649.51	-			
								20			20		LB	SEED	651.15	3.8			
								50			50		LB	FERTILIZER	651.18	-			
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20	0.3			
								0.5			0.5		TON	HAY MULCH	651.25	0.3			
							55				55		CY	TOPSOIL	651.35	0.5			
							30		64		94		SY	GRUBBING MATERIAL	651.40	1.8			

PROJECT NAME: BARTON
PROJECT NUMBER: BRO 1449(31)



FILE NAME: IJ068/cos/zlj068frm.dgn
PROJECT LEADER: J. BYATT
DESIGNED BY: M. HALEY
QUANTITY SHEET 2

PLOT DATE: 12/17/2014
DRAWN BY: S. GOODWIN
CHECKED BY: P. SHEDD
SHEET 10 OF 52