

QUANTITY SHEET 3

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | TOTALS | | DESCRIPTIONS | | | | DETAILED SUMMARY OF QUANTITIES | | | |
|---------------------------------|--|--|--|--|--|--|---------|-----------------|--------|-----------------|-------------|--------------|------|---|-------------|--------------------------------|------------|------|---|
| | | | | | | | ROADWAY | EROSION CONTROL | BRIDGE | FULL C.E. ITEMS | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND | QUANTITIES | UNIT | ITEMS |
| | | | | | | | | 1 | | | 1 | | LS | EPSC PLAN | 652.10 | - | | | |
| | | | | | | | | 40 | | | 40 | | HR | MONITORING EPSC PLAN | 652.20 | - | | | SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY) |
| | | | | | | | | 1 | | | 1 | | LU | MAINTENANCE OF EPSC PLAN (N.A.B.I.) | 652.30 | - | 200 | TON | TYPE IIS |
| | | | | | | | | 175 | | | 175 | | SY | TEMPORARY EROSION MATTING | 653.20 | 5 | 345 | TON | TYPE NS |
| | | | | | | | | 3 | | | 3 | | CY | TEMPORARY STONE CHECK DAM, TYPE I | 653.25 | EST. | 545 | TON | SUBTOTAL |
| | | | | | | | | 1 | | | 1 | | EACH | FILTER BAG | 653.45 | - | 5 | TON | ROUNDING |
| | | | | | | | 1320 | | | | 1320 | | LF | PROJECT DEMARCATION FENCE | 653.55 | 7 | 550 | TON | TOTAL |
| | | | | | | | 18 | | | | 18 | | SF | TRAFFIC SIGNS, TYPE A | 675.20 | 0.16 | | | |
| | | | | | | | 50 | | | | 50 | | LF | SQUARE TUBE SIGN POST AND ANCHOR | 675.341 | - | | | |
| | | | | | | | 7 | | | | 7 | | EACH | REMOVING SIGNS | 675.50 | - | | | |
| | | | | | | | 2 | | | | 2 | | EACH | ERECTING SALVAGED SIGNS | 675.60 | - | | | |
| | | | | | | | 1 | | | | 1 | | EACH | SETTING SALVAGED POSTS | 675.61 | - | | | |
| | | | | | | | 4 | | | | 4 | | EACH | DELINEATOR WITH STEEL POST | 676.10 | - | | | |
| | | | | | | | 1 | | | | 1 | | EACH | REMOVAL OF EXISTING DELINEATOR | 676.12 | - | | | |
| | | | | | | | 1 | | | | 1 | | LU | PRICE ADJUSTMENT, FUEL (N.A.B.I.) | 690.50 | - | | | |
| | | | | | | | | | 39 | | 39 | | CY | SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ) | 900.608 | 2.8 | | | |
| | | | | | | | | | 140 | | 140 | | LF | SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAMS) (NEXT 32 D) | 900.640 | - | | | |
| | | | | | | | 1 | | | | 1 | | LS | SPECIAL PROVISION (CPM SCHEDULE) | 900.645 | - | | | |
| | | | | | | | 1 | | | | 1 | | LU | SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.) | 900.650 | - | | | |
| | | | | | | | 1 | | | | 1 | | LU | SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.) | 900.650 | - | | | |
| | | | | | | | 1 | | | | 1 | | LU | SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.) | 900.650 | - | | | |
| | | | | | | | 65 | | | | 65 | | SY | SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRVES) | 900.675 | 2 | | | |
| | | | | | | | 550 | | | | 550 | | TON | SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY) | 900.680 | 5 | | | |

PROJECT NAME: BARTON
PROJECT NUMBER: BRO 1449(31)

FILE NAME: IJ068/cos/zlj068frm.dgn
PROJECT LEADER: J. BYATT
DESIGNED BY: M. HALEY
QUANTITY SHEET 3

PLOT DATE: 1/5/2015
DRAWN BY: S. GOODWIN
CHECKED BY: P. SHEDD
SHEET II OF 52

