

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
							EROSION CONTROL	ROADWAY	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10					
								1600			1600		CY	COMMON EXCAVATION	203.15					
									180		180		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27					
								820			820		CY	SAND BORROW	203.31					
								21			21		CY	TRENCH EXCAVATION OF EARTH	204.20					
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22					
									1040		1040		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30					
									1785		1785		CY	COFFERDAM EXCAVATION, EARTH	208.30					
									450		450		CY	COFFERDAM EXCAVATION, ROCK	208.35					
									1		1		LS	COFFERDAM (ABUTMENT NO. 1)	208.40					
									1		1		LS	COFFERDAM (ABUTMENT NO. 2)	208.40					
								900			900		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25					
								300			300		CY	AGGREGATE SURFACE COURSE	401.10					
									314		314		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34					
									29176		29176		LB	REINFORCING STEEL, LEVEL I	507.11					
									5		5		GAL	WATER REPELLENT, SILANE	514.10					
									225		225		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED DELETED CO #1	519.20					
									1		1		EACH	REMOVAL OF STRUCTURE (575 SF - EST.)	529.15					
								31			31		LF	18" CPEP	601.0915					
								1			1		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25					
								800	440		1240		CY	STONE FILL, TYPE II	613.11					
								165			165		LF	REMOVING AND RESETTNG FENCE	620.50					
								444			444		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20					
								4			4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60					
								166			166		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80					
								60			60		LF	TEMPORARY TRAFFIC BARRIER	621.90					
								32			32		HR	FLAGGERS	630.15					
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10					
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16					
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26					
								1			1		LS	MOBILIZATION/DEMobilIZATION	635.11					
								1			1		LS	TRAFFIC CONTROL	641.10					
								2050	750		2800		SY	GEOTEXTILE UNDER STONE FILL	649.31					
							100				100		SY	GEOTEXTILE FOR SILT FENCE	649.51					
							50				50		LB	SEED	651.15					
							110				110		LB	FERTILIZER	651.18					
							0.5				0.5		TON	AGRICULTURAL LIMESTONE	651.20					
							0.5				0.5		TON	HAY MULCH	651.25					
							10				10		CY	TOPSOIL	651.35					
									440		440		SY	GRUBBING MATERIAL	651.40					

PROJECT NAME: FAIRFIELD
 PROJECT NUMBER: BRO 1448(38)
 FILE NAME: z1j072qty.dgn
 PROJECT LEADER: D. LANDRY
 DESIGNED BY: T. TRAVER
 QUANTITY SHEET (1 OF 2)

PLOT DATE: 12-NOV-2013
 DRAWN BY: W. GAYNOR
 CHECKED BY: T. KENDRICK
 SHEET 6 OF 41

