

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							EROSION CONTROL	ROADWAY	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	EPSC PLAN	652.10				
							50				50		HR	MONITORING EPSC PLAN	652.20				
							1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I)	652.30				
							1055				1055		SY	TEMPORARY EROSION MATTING	653.20				
							80				80		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
							2				2		EACH	FILTER BAG	653.45				
							1225				1225		LF	PROJECT DEMARCATION FENCE	653.55				
								2			2		EACH	REMOVING SIGNS	675.50				
								6			6		EACH	DELINEATOR WITH FLEXIBLE POST	676.20				
									1		1		LS	SPECIAL PROVISION (COMPOSITE ARCH SUPERSTRUCTURE)	900.645				
									1		1		LS	SPECIAL PROVISION (CONCRETE ARCH SLAB ON FRP DECKING) DELETED CO #1	900.645				
									530		530		SF	SPECIAL PROVISION (FRP MECHANICALLY STABILIZED EARTH ARCH HEADWALLS)	900.670				
									1075		1075		SF	SPECIAL PROVISION (PRECAST CONCRETE GRAVITY RETAINING WALL)	900.670				

PROJECT NAME: FAIRFIELD
 PROJECT NUMBER: BRO 1448(38)
 FILE NAME: z11j072qty.dgn
 PROJECT LEADER: D. LANDRY
 DESIGNED BY: T. TRAVER
 QUANTITY SHEET (2 OF 2)

PLOT DATE: 01-NOV-2013
 DRAWN BY: W. GAYNOR
 CHECKED BY: T. KENDRICK
 SHEET 7 OF 41

