

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES								TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
						ROADWAY	EROSION CONTROL	BRIDGE 35	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						50				50		CY	TOPSOIL	651.35	5			
								121		121		SY	GRUBBING MATERIAL	651.40	0.1			
							1			1		LS	EPSC PLAN	652.10	-			
							50			50		HR	MONITORING EPSC PLAN	652.20	8			
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I)	652.30	-			
							150			150		SY	TEMPORARY EROSION MATTING	653.20	8			
							6			6		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	-			
							15			15		CY	VEHICLE TRACKING PAD	653.35	EST.			
							2			2		EACH	FILTER BAG	653.45	-			
						130				130		LF	BARRIER FENCE	653.50	5.8			
						350				350		LF	PROJECT DEMARCATION FENCE	653.55	0.9			
						1				1		EACH	REMOVING SIGNS	675.50	-			
						4				4		EACH	DELINEATOR WITH STEEL POST	676.10	-			
								18		18		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ)	900.608	1			
								109		109		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAMS) (NEXT 28 D)	900.640	-			

CLD 12-0175 MODEL: 02

PROJECT NAME: RANDOLPH  
PROJECT NUMBER: BRO 1444(57)



FILE NAME: z11j078qss.dgn  
PROJECT LEADER: J. BYATT  
DESIGNED BY: J. SMITH  
QUANTITY SHEET 2

PLOT DATE: 8/12/2014  
DRAWN BY: K. RUTTER  
CHECKED BY: D. MUNRO  
SHEET 8 OF 39